

1 030438

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 069-20,157-0000

NE NE NW, SEC. 3, T 29 S, R 30 W/E

4950 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6029

Lease Name Reed Well # 1

Operator: Ladd Petroleum Corp.

County Gray 238.88

Name & Address P. O. Box 2848

Well Total Depth 7350 feet

Tulsa, OK 74101

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1644

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 8:30 am Day: 18 Month: June Year: 19 85

Plugging proposal received from Bob Sargent

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 5308' Perfs at 4190-4204' CIBP at 4380 with 20' cement on top

1st plug pump 1 sack hulls and 30 sx cement

pump through 5 1/2" casing with mud between plugs

2nd plug at: 1650' with 40 sx cement

3rd plug at 660' with 30 sx cement

solid bridge

4th plug hulls - plug at 60' Plugging Proposal Received by Steve Durrant

cement to surface with 15 sx cement

Dick Kapp observed the plugging (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 10:00 am Day: 19 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 30 sx cement, 2nd plug at 1650'

with 40 sx cement, 3rd plug at 660' with 30 sx cement, 4th & 5th plugs - solid bridge -

hulls - plug at 60' -- cement to surface with 15 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

6-21-85 JUN 21 1985

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 2415' 5 1/2" casing. Used Common Cement by Sargent's

(If additional description is necessary, use BACK of this form.)

Dick Kapp observed the plugging.

(If you (operator) observe this plugging.

INVOICED

DATE 6-24-85

JUL 18 1985

Signed Steve Durrant (TECHNICIAN)

INV. NO. 8675 6-19