

1 060210  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

1-10

API NUMBER 15- 069-20,255-0000

App. C N/2 NW, SEC. 3, T 29 S, R 30 W X

660 feet from N & section line

1320 feet from W & section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3871

Lease Name Reed Well #1-3

Operator: Hugoton Energy Corporation

County Gray 183.30

Name: Address 229 E. William, Ste. 500

Well Total Depth 5460 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1663

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. Inc. License Number 30606

Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 10 Month: 1 Year: 1994

Plugging proposal received from Ed McKenna

(company name) Murfin Drilling Co. Inc. (phone) 316-267-3241

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1700' with 50 sx cement, 2nd plug at 750' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3 p.m. Day: 10 Month: 1 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 1700' with 50 sx cement,

2nd plug at 750' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

1-12-94  
1-12-94  
Rec'd  
J.M.

Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.  
(If additional description is necessary, use BACK of this form.)

DATE 1-28-94 I did not observe this plugging.

WELL NO. 39819

Signed Case Morris (TECHNICIAN)

INVOICED

1-10

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 12-20-93

State of Kansas

FORM MUST BE TYPED

DISTRICT # 1

NOTICE OF INTENTION TO DRILL 069-20,255-8000

FORM MUST BE SIGNED

SGA? Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well

ALL BLANKS MUST BE FILLED

Expected Spud Date 12 20 93  
month day year

Spot AC - N2 - NW Sec 3 Twp 29 S, Rg 30 x West East

OPERATOR: License # 3871  
Name: Hugoton Energy Corporation  
Address: 229 E. William, Suite 500  
City/State/Zip: Wichita, KS 67202  
Contact Person: Jim Gowens  
Phone: (316) 262-1522

660 FNL feet from North line of Section  
1320 FWL feet from West line of Section

IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

County: GRAY

Lease Name: REED Well #: 1-3

Field Name: US 56

Is this a Prorated/Spaced Field? yes x no

Target Formation(s): St. Louis

Nearest lease or unit boundary: 660'

Ground Surface Elevation: est. 2758 feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 250'

Depth to bottom of usable water: 700'

Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 1650'

Length of Conductor pipe required: NA

Projected Total Depth: 5600'

Formation at Total Depth: St. Louis

Water Source for Drilling Operations:

well farm pond X other

DWR Permit # \_\_\_\_\_

Will Cores Be Taken? yes X no

If yes, proposed zone: \_\_\_\_\_

CONTRACTOR: License #: 30606  
Name: Murfin Drilling Co., Inc.

Well Drilled For: Well Class: Type Equipment:

X Oil Enh Rec Infield X Mud Rotary  
X Gas Storage Pool Ext. Air Rotary  
OWWO Disposal X Wildcat Cable  
Seismic # of Holes Other  
Other

If OWWO: old well information as follows:

Operator: \_\_\_\_\_

Well Name: \_\_\_\_\_

Comp. Date \_\_\_\_\_ Old Total Depth \_\_\_\_\_

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth: \_\_\_\_\_

Bottom Hole Location \_\_\_\_\_

Exp. 6/15/94

AFFIDAVIT

720' Alt. I Req.

RECEIVED

KANSAS CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.  
It is agreed that the following minimum requirements will be met:

Pusher Ed McKauer  
SPUD DATE 12-29-93 INIT. SM  
LENGTH SURFACE PLANNED 1650'  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD? Y N SIZE HOLE \_\_\_\_\_  
SURFACE PIPE 3/4" @ 1663 CONDUCTOR \_\_\_\_\_  
ANHYDRITE T- B- ELEVATION \_\_\_\_\_  
TD 5460 FORMATION \_\_\_\_\_  
RAN PIPE @ DV TOOL ALT II DONE \_\_\_\_\_  
SX Y N  
Arbuckle Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Hug./Council @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Anhydrite Base @ 1700 Ft. W/ 50 SX  
1/2 Base Anhy. @ 750 Ft. W/ 50 SX  
1/2, 1/2 Plug @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
Bottom Surface @ \_\_\_\_\_ Ft. W/ \_\_\_\_\_ SX  
40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX  
WATER WELL \_\_\_\_\_ SX (Irr. Well \_\_\_\_\_ Pond \_\_\_\_\_)  
Hauling \_\_\_\_\_  
TECHNICIAN CR DATE 1-7-93  
TYPE OF CEMENT 60/40 600 1/4 # F.S.  
STARTING TIME 7:00 (AM/PM) DATE 1-10-94  
COMPLETION TIME 3:00 (AM/PM) DATE 1-10-94  
CEMENT COMPANY Allied