

1 090624

15-081-30091-0000

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Completed 6/7/66
C SW SE, SEC. 14, T 29 S, R 33 W/4
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952
Operator: Amoco Production Company
Name:
Address P.O. Box 800 Room 924
Denver, CO 80201

Lease Name E.W. Huitt Well # 1
County Haskell 188.50
Well Total Depth 5800 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 689

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address

Company to plug at: Hour: 2 p.m. Day: 16 Month: 11 Year: 19 95

Plugging proposal received from Bill Chatham

(company name) Amoco Production Co. (phone) 316-356-6939

logs: 5 1/2" at 5535' w/250 sx cement, PBTD 5410', Perfs at 4258-5400'

1st plug set CIBP at 4675' w/20 sx cement,

2nd plug set CIBP at 4200' with 20 sx cement, 3rd plug set CIBP at 3100', 4th plug perforate casing at 3050' and pump 80 sx cement, 5th plug set CIBP at 800', 6th plug perforate casing at 730' and pump in 175 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7 p.m. Day: 16 Month: 11 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4675' w/20 sx cement,

2nd plug set CIBP at 4200' w/20 sx cement,

3rd plug set CIBP at 3100',

4th plug perforate casing at 3050' and pump 80 sx cement,

5th plug set CIBP at 800',

6th plug perforate casing at 730' and pump 175 sx cement.

Cement circulated to surface.

Remarks: Used 65/35 Pozmix 8% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 27 1995

INV. NO. 44116

11-16

RECEIVED
STATE CORPORATION COMMISSION
1995
CONSERVATION DIVISION
Wichita, Kansas

11-21-95

Signed [Signature] (TECHNICIAN)