

To: 1 020732 12-21  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-081-20,748-0000  
SW SW NE NE, SEC. 14, T 29 S, R 33  
4030 feet from S section line  
1250 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5269  
Operator: Kansas Natural Gas, Inc.  
Name:  
Address P.O. Box 815  
Sublette, KS 67877

Lease Name Alleman Well # 1-2  
County Haskell  
Well Total Depth 2793 90.77 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 727

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kansas Natural Gas, Inc. License Number 5269

Address P.O. Box 815, Sublette, KS 67877

Company to plug at: Hour: 8 a.m. Day: 21 Month: 12 Year: 19 93

Plugging proposal received from Steve Lehning

(company name) Kansas Natural Gas, Inc. (phone) 316-675-8185

Work: 5 1/2" at 2789' w/600 sx cement, Perfs at 2673-83, 2698-2706, 2715-21'

1st plug run cement retainer to 2400', pump 50 sx cement, pull out of retainer,

2nd plug pull tubing to 1500' and pump 40 sx cement,

3rd plug pull tubing to 780' and pump 40 sx cement,

4th plug pull tubing to 60' and set 10 sx plug.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:45 p.m. Day: 21 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug ran cement retainer to 2400', pumped 50 sx cement-Class H.

Pull out of retainer,

2nd plug pulled tubing to 1878' and pumped 40 sx cement,

3rd plug pumped 40 sx cement at 780',

4th plug pumped 10 sx cement at 60'-to -4'.

Pressured up annulus.

Used Class C 2% cc cement by Halliburton. No casing recovery

If additional description is necessary, use BACK of form.

INVOICED  
DATE 1-7-94  
INV. NO. 39643

Signed Glenn Barlow (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 03 1994  
CONSERVATION DIVISION  
Wichita, Kansas