

To: 1051623 3-10

15-081-00398-0000  
API NUMBER 15- Drilled 1/14/54

172

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW SE NW, SEC. 33, T 29 S, R 32 W XX

2970 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5269

Lease Name Murphy Well # 1

Operator: Kansas Natural Gas, Inc.  
Name & Address P.O. Box 818  
Hays, KS 67601

County Haskell

Well Total Depth 2754 89.50 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 519

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: 1 p.m. Day: 10 Month: 3 Year: 1993

Plugging proposal received from Steve Lehning

(company name) Kansas Natural Gas, Inc. (phone) 316-675-8185

were: 7" at 2754' w/700 sx cement, Perfs at 2664-72, 2694-2710'

Tubing & rods parted at 1524'. They fished on them for two weeks.

1st plug set CIBP at 1500',

2nd plug run in with tubing to 650' and circulate cement to surface.

3rd plug hook onto backside and pump into if possible.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:40 p.m. Day: 10 Month: 3 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 1490'

2nd plug ran tubing to 662' and circulated cement to surface with 100 sx.

10 3/4" X 7" annulus full of cement-checked by visual inspection.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 15 1993  
3-15-93

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 65/35 Pozmix 8% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE 3-24-93

INV. NO. 37506

Signed Richard M. Lacy  
(TECHNICIAN)

Handwritten initials