

1 020200

1-6

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 081-00047 - 0002  
NW SE, SEC. 33, T 29 S, R 33 (W/E)

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952  
Operator: Amoco Production Company  
Name:  
Address P.O. Box 800  
Denver, CO 80201

1980 feet from S section line  
1980 feet from E section line  
Lease Name Preedy G.U. Well # 1  
County Haskell 177.26  
Well Total Depth 5454 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1852

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Midwest Casing Pullers License Number 6497  
Address Box F, Sublette, KS 67877

Company to plug at: Hour: 9:30 a.m. Day: 5 Month: 1 Year: 19 89

Plugging proposal received from Ed Eyes  
(company name) Midwest Casing Pullers (phone) 316-675-8349

were: 5 1/2" at 5450' PBD 5414' Perfs at 5309-11, 4885-87, 4668-80, 4462-68, 4419-23'  
1st plug set CIBP at 4375' with 2 sx cement on top,  
2nd plug pump 45 sx cement at 1900-1725',  
3rd plug pump 90 sx cement at 600-250',  
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Glenn R. Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None  
Operations Completed: Hour: 2:30 p.m. Day: 6 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4375' with 2 sx cement on top,  
2nd plug loaded hole with mud and pumped 45 sx cement at 1900-1725',  
3rd plug pumped 90 sx cement at 600-250',  
4th plug pumped 10 sx cement at 40-4'.

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 10 1989  
1-10-89  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Midwest Casing Pulling. Recovered 2050' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 1-12-89  
INV. NO. 23642

Signed Glenn R. Barlow  
(TECHNICIAN)