

To: 100160

9-12

API NUMBER 15-081-20,181-0000

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION SE SE NE NW, SEC. 11, T 29 S, R 34 W XX
130 S. Market, Room 2078
Wichita, KS 67202

4030 feet from S section line

2880 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4824

Lease Name Wright Well # 3

Operator: Mesa Operating Co.

County Haskell 100.91

Name & Address 5205 N. O'Connor Blvd., Ste. 1400W

Well Total Depth 3105 feet

Irving, TX 75039

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 667

Abandoned Oil Well _____ Gas Well Input Well _____ SKD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Border-Line, Inc. License Number 7840

Address RR 3, Box 1043, Ulysses, KS 67880-1043

Company to plug at: Hour: 9 a.m. Day: 11 Month: 9 Year: 19 97

Plugging proposal received from Tim Lewis.

(company name) Mesa Operating Co. (phone) 972-444-9001

were: 4 1/2" at 3100' w/300 sx cement. Perfs at 2844-2944'

1st plug set CIBP at 2825' with 20' cement on top,

2nd plug at 1770' with 80 sx cement,

3rd plug at 700' with 50 sx cement,

4th plug at 40' with 10 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 17 1997

9-17-97

CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 12 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2825' with 2 sx cement on top,

Load hole with mud to 775',

2nd plug pumped 20 sx cement, displaced to 520',

3rd plug perforated 4 1/2" casing at 325' and pumped 95 sx cement. No circulation. Let set

overnight. 9/12/95 Tagged cement at 230'. 4th plug pumped 40 sx cement down 4 1/2" casing,

5th plug pumped 60 sx cement down backside, pressured to 500 psi and held.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

I (did / observed) observe this plugging.

DATE 9-23-97

Signed Gary Winters (TECHNICIAN)

INV. NO. 49083