

1 060474

15-081-00141-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 1-15-45

W

NW NW SE , SEC. 11 , T 29 S, R 34
2540 feet from S section line
2540 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5575

Lease Name J.B. Wright Well # 1

Operator: Mesa Petroleum Co.

County Haskell 89.15

Named Address P. O. Box 2009

Well Total Depth 2743 feet

Amarillo, TX 79189

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 660

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 10:00 am Day: 30 Month: January Year: 19 85

Plugging proposal received from Tom Hahn

(company name) Sargent's (phone) 316-624-7455

were: 7" set at 2543' PBDT 2712' Perfs at 2502-2541 5 1/2" liner at 2485-2712

Pipe collapsed at 1859' and hole to that depth was full of sand

RECEIVED

Spotted plugs through 7" casing with mud between plugs

STATE CORPORATION COMMISSION

1st plug on stub at 1010' with 40 sx cement

2-4-85
FEB 04 1985

2nd plug at 700' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part x None

Operations Completed: Hour: 11:30 am Day: 30 Month: January Year: 19 85

ACTUAL PLUGGING REPORT Pipe collapsed at 1859' and hole to that depth was full of sand.

Spotted plugs through 7" casing with mud between plugs - 1st plug on stub at 1010'

with 40 sx cement, 2nd plug at 700' with 40 sx cement, 3rd & 4th plugs - solid bridge -

hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: Recovered 1020' 7" casing. Used Common Sacked cement by Sargent's.

(if additional description is necessary, use BACK of this form.)

INVOICED

(if desired) observe this plugging.

DATE 2-8-85

Signed Paul A. Luthi (TECHNICIAN)

INV. NO. 6892 1-30