

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20357-00-00  
Spot: CNW Sec/Twnshp/Rge: 11-29S-34W  
3960 feet from S Section Line, 3960 feet from E Section Line  
Lease/Unit Name: WRIGHT Well Number: 4-11  
County: HASKELL Total Vertical Depth: 3000 feet

Operator License No.: 4824 Conductor Pipe: Size feet: 8 97.50  
Op Name: PIONEER NATURAL RESOURCES USA, I Surface Casing: Size 8.625 feet: 820 WITH 400 SX CMT  
Address: 5205 N. O'CONNOR BLVD. Production: Size 5.5 feet: 3000 WITH 225 SX CMT  
IRVING, TX 75039 Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/12/2002 10:00 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PLUG AT 1900' WITH HULLS & 20 SX CMT. PLUG AT 1350' WITH HULLS & 30 SX CMT. PLUG AT 840' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 11/12/2002 5:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:  
PERFS AT 2549-2742'. TUBING FISH IN HOLE @ 1984' & CASING LEAK AT 1349'. 1ST PLUG RAN TUBING IN HOLE TO 1900'. CIRCULATE HOLE WITH MUD. PUMP 20 SX CMT WITH HULLS & DISPLACED WITH 6 BBLs MUD. 2ND PLUG PULL TO 1400' & PUMP 30 SX CMT WITH HULLS. DISPLACED WITH 4 BBLs MUD. TRIP OUT OF HOLE WITH 2 3/8". SHOT CASING AT 925'. 3RD PLUG PULLED UP TO 840' & PUMPED 50 SX CMT. 4TH PLUG PULLED UP TO 40' & PUMPED 10 SX CMT.

RECEIVED  
NOV 20 2002 11-20-02  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 925' OF 5 1/2" CASING.

Plugged through: CSG

District: 01 Signed Kevin D Strube (TECHNICIAN)  
  
  
