

To: 1 100095 2-11  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15-081-20,955-0000  
489' N & 185' E of  
C NE NE, SEC. 16, T 29 S, R 34  
171 feet from NSX section line  
475 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4549  
Operator: Anadarko Petroleum Corporation  
Name & Address: P.O. Box 351  
Liberal, KS 67905-0351

Lease Name Owens A Well # 3  
County Haskell 186.94  
Well Total Depth 5752 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1806

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent & Horton Plugging, Inc. License Number 31151  
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 2 p.m. Day: 10 Month: 2 Year: 19 97  
Plugging proposal received from Don Horton  
(company name) Sargent & Horton Plugging, Inc. (phone) 405-854-6515

logs: 5 1/2" at 5728' w/370'sx cement, PBD 5375', Perfs at 5455-5544, 5406-24, 5331-47, 5218-22'  
CIBP @ 5440', RPB @ 5365'

1st plug pump 2 sx hulls and 200 sx cement from 5375-5150',  
2nd plug set CIBP at 2650' with 2 sx cement on top, 3rd plug run free point, shoot off casing  
and pump 75 sx cement at cut off.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 1 p.m. Day: 11 Month: 2 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug pumped 200 sx cement with 4 sx hulls and displaced  
5375-5150',  
2nd plug set bridge plug at 2650', ran free point, cut off at 2400',  
3rd plug pumped 75 sx cement at 2400'.  
Plan to move rig back in to angle drill in the future.

Remarks: Used common cement by Sargent & Horton and Class H by Halliburton. Recovered 2400' of  
(If additional description is necessary, use BACK of this form.) 5 1/2" casing.

1. (If desired) observe this plugging.

DATE FEB 13 1997

Signed Gary Winters (TECHNICIAN)

INV. NO. 47559

FORM CP-2/3 Rev. 01-84

2-11 APR 25 1997

RE Completed

RECEIVED  
KANSAS CORP COM  
FEB 13 12:57

2-13-97