

1 050780

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,774-0006
C NE SW, SEC. 35, T 28 S, R 13 W/EX
1980 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363
Operator: Berexco, Inc.
Name & Address 970 Fourth Financial Center
Wichita, KS 67202

Lease Name Hanna-Wald Well # 1
County Pratt 155.68
Well Total Depth 4790 Arbuckle feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 385

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Beredco, Inc. License Number 5147
Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 10:00 am Day: 19 Month: March Year: 19 86

Plugging proposal received from Gary Marshall
(company name) Beredco (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 850' Elevation 1925 est.

1st plug at 4800' (est) in the Arbuckle with 40 sx cement

2nd plug at 860' (est) at the base of the Anhydrite with 50 sx cement

3rd plug at 390' 30" below the base of the surface pipe with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:00 am Day: 19 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 4750' with 40 sx cement, 2nd plug at 850' with 50 sx cement, 3rd plug at 390' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(If additional description is necessary, use BACK of this form.)

INVOICED
MAR 20 1986

DATE
INV. NO. 13016
3-19

STATE CORPORATION COMMISSION
Signed Richard Lacey (TECHNICIAN)

MAR 20 1986
CONSERVATION DIVISION
Wichita, Kansas
3-20-1986