

To: 1 041164
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-151-22,093-0000

SW SW NW, SEC. 35, T 28 S, R 13 W/E

2310 feet from NY section line

.330 feet from WE section line

4-17

TECHNICIAN'S PLUGGING REPORT

Operator License # 4253

Lease Name Fincham Well # 1

Operator: Plains Petroleum Operating Company

County Pratt 159.25

Name & Address P.O. Box 383

Well Total Depth 4900 feet

Lakin, KS 67860

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 369

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 12 p.m. Day: 17 Month: 4 Year: 19 96

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

logs: 5 1/2" at 4892' w/250 sx cement, PBD 4858', Perfs at 4266-71, 4413-32, 4544-62, CIBP at 4675'

1st plug pump 3 sx hulls and 25 sx cement,

2nd plug at 780-800' with 50 sx cement,

3rd plug at 400' with 75 sx cement,

4th plug at 40' with 18 sx cement.

Plugging Proposal Received by Steve Pfeifer

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 17 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 300 lbs. hulls and 25 sx cement, Loaded hole with drilling mud and spotted plugs through 5 1/2" casing.

2nd plug at 780' with 50 sx cement,

3rd plug at 400' with 75 sx cement,

4th plug at 40' with 18 sx cement.

Remarks: Used common cement by Sargent's. Recovered 3220' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

Invited observer to observe this plugging.

INVOICED

DATE APR 24 1996

INV. NO. 45437

4-17

Signed Steve Pfeifer
(TECHNICIAN)

FORM CP-2
REV. 01-84

RECEIVED
KANSAS CORP COM
1996 APR 23 11:07
4-23-1996