

1 030448

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,617-6000

NW SW SW<sup>1</sup>, SEC. 33, T 28 S, R 13 W/E

990 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5399

Lease Name Eubank Trust Well # "A" 1

Operator: American Energies Corporation

County Pratt 150.32

Name & Address 575 Fourth Financial Center

Well Total Depth 4625 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 11:30 pm Day: 21 Month: June Year: 19 85

Plugging proposal received from Dennis Petz

(company name) Wheatstate (phone) 316-672-7514

Elevation 1939'

Remarks: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 760'

1st plug at 790' with 50 sx cement

2nd plug at 330' with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Put 5 sx cement in water well

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:15 am Day: 22 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 790' with 50 sx cement, 2nd plug at 330' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement and plugged water well with

5 sx cement.

RECEIVED

STATE CORPORATION COMMISSION

7-1-1985

JUL 01 1985

Remarks: Used Light cement 2% gel 3% cc by Buie.

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(Please do not) observe this plugging.

DATE 7-10-85

Signed Steve Durrant

(TECHNICIAN)

INV. NO. 8786