

1 010263

JUN 22 1987

API NUMBER ~~15-NA 151~~ - 20532-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NE NW, SEC. 21, T 28 S, R 13 W/E
4290 feet from S section line

TECHNICIAN'S PLUGGING REPORT

3630 feet from E section line

Operator License # 3055

Lease Name Hamilton Well # 1

Operator: Petrie Exploration

County: Pratt 105.63

Name & Address: Route #1

Well Total Depth 3250 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 205

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 12:30 p.m. Day: 22 Month: 6 Year: 19 87

Plugging proposal received from Stanley Petrie

(company name) Petrie Exploration (phone) 316-672-6236

were: 4 1/2" at 3250' PBD 3210' Perfs at 3125-28'

1st plug pump 25 sx common cement and stop plug at 2232',

2nd plug pump 50 sx cement at 820',

3rd plug pump 50 sx cement at 230',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:10 p.m. Day: 22 Month: 6 Year: 19 87

ACTUAL PLUGGING REPORT Hit old cement at 153'. Drilled about 20' of hard cement, went in with tubing to 829'. Plugged through tubing first.

1st plug at 826' with 50 sx cement,

2nd plug at 216' with 50 sx cement,

3rd plug at 40'-0" with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUN 30 1987

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1500' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 7-1-87

Signed [Signature] (TECHNICIAN)

INV. NO. 17403

6-22 JUL 30 1987