

1060300

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,457-0000

SW SE NW, SEC. 2, T 28 S, R 13 W/R  
2970 feet from N SE Corner of ~~KXS~~ section line  
3520 feet from W SE Corner of ~~KXS~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9623

Lease Name Green Well # 22-3-2

Operator: Phelps Dodge Fuel Dev. Corp.  
Name & Address: 1225 17th St., Suite 2200  
Denver, CO 80202

County Pratt

Well Total Depth 4591 149.21 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1104

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sterling Drilling Company License Number 5142

Address Box 129, 6th & Cleveland, Sterling, KS 67579

Company to plug at: Hour: 9:00 am Day: 16 Month: August Year: 19 84

Plugging proposal received from Dave Branden

(company name) Phelps Dodge (phone) 303-296-0128

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1150' with 50 sx cement

2nd plug at 520' with 30 sx cement  
solid bridge

3rd plug hulls' - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthie (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:15 am Day: 16 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1150' with 50 sx cement, 2nd plug at 520' with 30 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

AUG 24 1984

8-24-1984

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED (check if not) observe this plugging.

Signed Paul A. Luthie SD (TECHNICIAN)

DATE 8-29-84

INV. NO. 3455