

2 040258

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-095-20307-0000

NWNE, SEC. 20, T. 28 S, R. 9 WB

4620 feet from N(S) section line

1980 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Houser Well # 1

Operator: NCRA / Frank Black

County Kingman 145.44

Name & Address Box 6

Well Total Depth 4475 feet

Great Bend Ks. 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 286

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address Genesco Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____

RECEIVED

Plugging proposal received from Alan Nicholas

STATE CORPORATION COMMISSION

(company name) Nicholas Casing Pulling (phd) MAR 24 1986

were: _____ CONSERVATION DIVISION
Wichita, Kansas

PBTD 4390 Sand to 4030 @ 4 sks. 3-24-1986
4 1/2" 4469 175 sk 2 Hulls 12 gel 60 sks Howco-Lite
Perf 4078-84

Plugging Proposal Received by S Vandusen & W Kerkpatrick
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 1:00 Day: 10 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT The perforations were sandbed back
to 4030' and 4 sacks of cement spotted on top of the sand
thru the dump trailer. The 4 1/2" was shot off and
recovered from 3183'. The top was squeezed thru the
8 5/8" surface casing by pumping 2 sacks of hulls, 12 sacks
of gel and 60 sacks of HOWCO-LITE cement.

Remarks: HOWCO # 436066 MX 500 # SJ 425 #
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE MAR 25 1986
INV. NO. 13103

WK

Signed [Signature]
(TECHNICIAN)

RQ