

2 060464

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 095-21,567 .000  
N/2 SE, SEC. 26, T 28 S, R 7 W/EX

1980 feet from S section line  
1320 feet from E section line

Lease Name Mayer A Well # 1  
County Kingman 69.94

Well Total Depth 2152 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 271

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling License Number \_\_\_\_\_

Address \_\_\_\_\_

Company to plug at: Hour: \_\_\_\_\_ Day: 31 Month: 3 Year: 19 87

Plugging proposal received from Charles Paulson

(company name) Duke Drilling (phone) \_\_\_\_\_

were: Condition hole

35 sacks at 900'

35 sacks at 325'

Push W.R. plug to 60' and circulate 75 sacks cement to surface. Run

drill pipe rathole and circulate 10 sacks. Circulate 5 sacks in water well.

Plugging Proposal Received by Ron Wilson (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:00 pm Day: 31 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT Conditioned hole and ran drill pipe to approximately 900'.

B.J. Titan spotted 35 sacks cement. Pulled drill pipe to approximately 375' and spotted

35 sacks cement. Pushed wood-rubber plug to approximately 60' and circulated 25 sacks

to surface. Ran pipe in rathole and circulated 10 sacks. Circulated 5 sacks in

water well.

RECEIVED  
STATE CORPORATION COMMISSION

APR 2 1987

Remarks: B.J. Titan #244856

(If additional description is necessary, use BACK OF THIS FORM.)

INVOICED

(XXXX) do not observe this plugging.

DATE 4-3-87

Signed [Signature] (TECHNICIAN)

INV. NO. 16474