

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-21064-00-00
Spot: E2NWNE Sec/Twnshp/Rge: 27-29S-18W
4620 feet from S Section Line, 1886 feet from E Section Line
Lease/Unit Name: LANDEN - A TRUST Well Number: 1
County: KIOWA Total Vertical Depth: 4950 feet

Operator License No.: 5004
Op Name: VINCENT OIL CORPORATION
Address: 125 N. MARKET, STE 1075
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 538 WITH 300 SX CMT
Production: Size 4.5 feet: 4870 WITH 125 SX CMT
Liner: Size _____ feet:

5/60-88

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/13/2001 8:30 AM
Plug Co. License No.: 4072 Plug Co. Name: PLAINS INC
Proposal Rcvd. from: PAT LIVINGSTON Company: VINCENT OIL Phone: (316) 546-3316

Proposed Plugging Method: CIBP @ 4700' & 2 SX CMT ON TOP. 1ST PLUG AT 1390' WITH 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT. USE 15 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/13/2001 11:45 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4751-4756'. SET CIBP @ 4700' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1390' WITH 50 SX CMT. 2ND PLUG AT 560' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

INVOICED

DATE 8-31-01

INV. NO. 2002060315

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2500' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed _____

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED

AUG 31 2001
KCC WICHITA

8-31-2001

AUG 20 2001

MP

Form *CP-213*