

1 090381

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-097-21,149-0000

S/2 SW SE, SEC. 29, T 29 S, R 18 (W/EX)

330 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Yost "A" Well # 2

Operator: TXO Production Corporation

County Kiowa 162.99

Name & Address 200 W. Douglas, Suite 300

Well Total Depth 5015 Mississippi feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 443

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor FWA Drilling Co., Inc. License Number 6165

Address P. O. Box 970, Yukon, OK 73099

Company to plug at: Hour: 3:00 am Day: 5 Month: October Year: 1985

Plugging proposal received from Allen Dick

(company name) TXO (phone) 316-265-9441

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2241'  
Anhydrite 1160'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 480' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Robert B. Tarbutton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 5:00 am Day: 5 Month: October Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 1160' with 50 sx cement, 2nd plug at 480' with 50  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to  
circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 15 1985 10-15-1985

Remarks: Used 60/40 Pozmix 6% gel by Halliburton  
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

Signed R B Tarbutton  
(TECHNICIAN)

INVOICED

DATE OCT 17 1985

INV. NO. 10674 NOV-13 1985

CARD MUST BE TYPED

State of Kansas  
NOTICE OF INTENTION TO DRILL  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: July 5 1985  
month day year

API Number 15-097-21,149-0000

OPERATOR: License # 5171  
Name TXQ Production Corp.  
Address 200 W. Douglas, Suite 300  
City/State/Zip Wichita, KS 67202  
Contact Person Jerry W. Collins  
Phone 316-265-9441

S/2 SW SE Sec 29 Twp 29 S Rge 18  
(location)  
330 Ft North from Southeast Corner of Section  
1980 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6165  
Name FWA Drilling Co., Inc.  
City/State Yukon, OK 73085

Nearest lease or unit boundary line 330 feet.  
County Kiowa  
Lease Name YOST "A" Well # 2

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mud Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

If OWWO: old well info as follows:  
Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 5100 feet  
Projected Formation at TD Miss  
Expected Producing Formations Miss

Depth to Bottom of fresh water 100 feet  
Lowest usable water formation Unknown  
Depth to Bottom of usable water 200 feet  
Surface pipe by Alternate: 1  2   
Surface pipe to be set 400 feet  
Conductor pipe if any required 0 feet  
Ground surface elevation TBD feet MSL  
This Authorization Expires 12-5-85  
Approved By 6-5-85 RCH FOR KDFE

certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 6-4-85 Signature of Operator or Agent Jerry W. Collins

Date 6-5-85 Drlg & Completion Engr. RCH FOR KDFE

Form C-1 4/84

Allen Beck - 435 85/8 - 9/28/85

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 15 1985  
CONSERVATION DIVISION  
Wichita, Kansas