

1041343

TO: STATE CORPORATION COMMISSION

3-29

API NUMBER ¹¹² 15-097-21,526-0000
SW SE SE SEC. 29, T 29 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME YOST "A" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 164.32

OPERATOR LICENSE # 31925

WELL TOTAL DEPTH 5056 FEET

OPERATOR: QUALITY WELL SERVICE ^{ok}

PRODUCTION CSG: SIZE 4 1/2" @ 5055' WITH 200 SX

NAME AND 249 BETH DRIVE

SURFACE CASING: SIZE 8 5/8" @ 476' WITH 350 SX

ADDRESS STERLING, KS 67579

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 1:45 PM DAY: 29 MONTH: 03 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410 4-8-1999

WERE: PERFS AT 4921-29, CIBP @ 4910, PERFS AT 4789-93, 4455-65

1ST PLUG SAND BACK TO 4400' WITH 4 SX CEMENT.

2ND PLUG AT 1200' WITH 50 SX CEMENT.

3RD PLUG AT 500' WITH 50 SX CEMENT.

4TH PLUG AT 0-40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 29 MONTH: 03 YEAR: 1999

ACTUAL PLUGGING REPORT _____

1ST PLUG SANDED BACK TO 4400' AND PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER.

LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING.

2ND PLUG AT 1240' WITH 50 SX CEMENT.

3RD PLUG AT 350' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2200' OF 4 1/2" CASING.

3RD PLUG WAS TO BE @ 500'. PLUG CONTRACTOR OFF ON JOINT COUNT. BASE OF THIRD PLUG AT 350'

PLUG SATISFACTORY. DIDN'T NEED TO CLEAN OUT. BASE OF FRESH WATER=220'. USABLE = 260'.

IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 4-9-99

SIGNED Steve Danndt

(TECHNICIAN)

FORM CP-2/3

INV. NO. 60812

RECEIVED
KANSAS CORP DIV
999 APR -8 12:15