

1090991

TO: STATE CORPORATION COMMISSION

4-1

API NUMBER 15-097-21,079-0000
E/2 NW SE SEC. 16, T 29 S, R 18 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME STAGAARD WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA

OPERATOR LICENSE # 31925

WELL TOTAL DEPTH 4985 162.02 FEET

OPERATOR: QUALITY WELL SERVICE PRODUCTION CSG: SIZE 5 1/2" @ 4971' WITH 75 SX

NAME AND 249 BETH DRIVE SURFACE CASING: SIZE 8 5/8" @ 516' WITH 300 SX

ADDRESS STERLING, KS 67579

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS SAME AS ABOVE

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 01 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4898-4902

1ST PLUG SAND TO 4850' WITH 5 SX CEMENT ON TOP.

2ND PLUG PULL TO 1150'. PUMP 6 SX GEL. SPOT 50 SX CEMENT.

3RD PLUG PULL TO 550' AND SPOT 50 SX CEMENT.

4TH PLUG PULL TO 40' CIRCULATE CEMENT TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 01 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 4850 WITH 5 SX CEMENT ON TOP.

2ND PLUG PULL TO 1150' PUMP 6 SX GEL. SPOT 50 SX CEMENT.

3RD PLUG PULL TO 550' AND SPOT 50 SX CEMENT.

4TH PLUG PULL TO 40' AND CIRCULATE CEMENT TO SURFACE. STAYED FULL.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1600' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

SIGNED

(TECHNICIAN)

FORM CP-2/3

DATE APR 16 1999

APR - 7 1999

4-7-1999

INV. NO. 6085

CONSERVATION DIVISION
Wichita, Kansas