

10-26

To: 1 061154
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 097-21,253 - 0000

NW SW NW, SEC. 16, T 29 S, R 18 W/E
3400 feet from S section line
4770 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8222

Lease Name Hadley Well # 1

Operator: Buttonwood Petroleum, Inc.
Name & Address: 9 East 4th Street, Suite 605
Tulsa, OK 74103

County Kiowa 164.13
Well Total Depth 5050 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 525

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Good Well Service Company License Number 8343

Address Woodward, OK

Company to plug at: Hour: 8 a.m. Day: 26 Month: 10 Year: 19 88

Plugging proposal received from Nel Howard

(company name) Buttonwood Petroleum, Inc. (phone) 405-939-2460

were: 4 1/2" at 5049' PBTB 5010' Perfs at 4950-54'
1st plug set CIBP at 4900' with 2 sx cement on top,
2nd plug at 1215' with 50 sx cement,
3rd plug at 625' with 75 sx cement,
4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:40 a.m. Day: 26 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4900' with 2 sx cement on top,

2nd plug at 1215' with 50 sx cement

3rd plug at 625' with 75 sx cement

4th plug at 40-0' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 27 1988 10-27-1988

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Western. Recovered 2552' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 10-31-88

INV. NO. 22844
10-26

DEC 9 1988