

9-22-87

To: 1 120020
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 20' S C SW SW, SEC. 14, T 29 S, R 18 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,151-0000
970 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: TXO Production Corporation
Name & Address: 155 North Market, Suite 1000
Wichita, KS 67202

Lease Name Unruh "B" Well # 5
County Kiowa 157.98
Well Total Depth 4861 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 518

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 22 Month: 9 Year: 1987

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pulling (phone) 316-793-9711

were: 4 1/2" at 4849' Open hole from 4850-61'

1st plug pump 2 sx hulls and 25 sx cement,

2nd plug pump 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:45 p.m. Day: 22 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT 1st plug pumped 25 sx cement and pushed plug to 4600' in 4 1/2" casing,

2nd plug pumped in 8 5/8" surface casing with 200 lbs. hulls, 15 sx gel, 50 lbs. hulls,

50 sx cement, 10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 29 1987 9-29-1987

Pumping pressure 400-1000 psi and shut in pressure 550 psi.

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3120' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Susan Rankin (TECHNICIAN)

DATE 10-7-87

INV. NO. 18407