

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-157-21,192 <sup>100-00</sup>

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Leben Drilling Co.

Complete Address 1055 Broadway, Wichita Kansas 67202

Lease Name Betschant Well No. 1

Location C-NW Sec. 4 Twp. 28 Rge. 15 (East)(West)

County Pratt Total Depth 4800'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Leben Drilling Co. Rig 11

Address 1055 Broadway Wichita Kans 67202 License No. 5888

Operation Completed: Hour: 1:30 P.M. Day: 27 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

1st plug @ 1200' w/ 50 sbp 2nd plug @ 450' w/ 40 sbp  
cent. 3rd plug on solid bridge @ 40' to 0' w/ 10 sbp cent.  
Then circulated 10 sbp cent. in rat hole & 5 sbp cent. in mouse  
hole. Cement used was 50/50 poz mix w/ 4% gill & 3% cc.  
The cement was pumped through drill pipe with  
hole full of heavy mud. The plugging was  
accomplished by sun cementing.

Amount of Surface Casing: 8 5/8" @ 394' cent. circulated

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Paul A. Luthie  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION

OCT 01 1982  
10-1-82

Signed: \_\_\_\_\_  
Conservation Division Agent  
Wichita, Kansas

INVOICED

DATE 10-20-82

INV. NO. 1413-W

\$ 156.00

1994