

ORIGINAL

SIDE ONE


STATE CORPORATION COMMISSION OF KANSAS  
OIL & GAS CONSERVATION DIVISION  
RECOMPLETION FORM  
ACO-2 AMENDMENT TO WELL HISTORY

API NO. 15- 151-21461-00-00  
County Pratt  
N/2 NE SW Sec. 29 Twp. 29 Rge. 12  East West  
2310 Ft. North from Southeast Corner of Section  
3300 Ft. West from Southeast Corner of Section  
(NOTE: Locate well in section plat below.)  
Lease Name Hearn Well # 1-29  
Field Name Hirt Ext.  
Producing Formation Mississippi  
Elevation: Ground 1878 KB 1890

Operator: License # 5056  
Name: F. G. Holl Company  
Address: P.O. Box 780167  
City/State/Zip: Wichita, Ks. 67278-0167  
Purchaser: Clear Creek  
Operator Contact Person: Elwyn H. Nagel  
Phone: (316) 684-8481

Designate Type of Original Completion  
 New Well  Re-Entry  Workover  
Date of Original Completion 8-11-84  
Name of Original Operator TXO Production Corp  
Original Well Name Hearn No. 1  
Date of Recompletion: 1-31-90 2-14-90  
Commenced Completed  
Re-entry  Workover

Designate Type of Recompletion/Workover:  
 Oil  SWD  Temp. Abd.  
 Gas  Inj  Delayed Comp.  
 Dry  Other (Core, Water Supply, etc.)  
 Deepening  Re-perforation  
 Plug Back  PBTD  
 Conversion to Injection/Disposal  
Is recompleted production:  
 Commingled  Docket No. \_\_\_\_\_  
 Dual Completion  Docket No. \_\_\_\_\_  
 Other (Disposal or Injection?)  Docket No. \_\_\_\_\_



RECEIVED  
STATE CORPORATION COMMISSION  
Wichita, Kansas  
MAY 22 1990

K.C.C. OFFICE USE ONLY  
 Letter of Confidentiality Attached  
 Wireline Log Received  
 Drillers Timelog Received  
Distribution  
 KCC  SWD/Rep  NGPA  
 KGS  Plug  Other (Specify)

INSTRUCTIONS: This form shall be completed in triplicate and filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within 120 days of the recompletion of any well. Rules 82-3-107 and 82-3-141 apply. Information on side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form. See rule 82-3-107 for confidentiality in excess of 12 months. One copy of any additional wireline logs and driller's time logs (not previously submitted) shall be attached with this form. Submit ACO-4 or ACO-5 prior to or with this form for approval of commingling or dual completions. Submit CP-1 with all plugged wells. Submit CP-111 with all temporarily abandoned wells. NOTE: Conversion of wells to either disposal or injection must receive approval before use; submit form U-1.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.  
Signature Elwyn H. Nagel Title Elwyn H. Nagel, Manager Date 5/22/90  
Subscribed and sworn to before me this 22nd day of May 19 90  
Notary Public V. Jean Feil Date Commission Expires \_\_\_\_\_



FORM ACO-2  
7/89

PI X

ORIGINAL

SIDE TWO

Operator Name F. G. Holl Company Lease Name Hearn Well # 1-29

Sec. 29 Twp. 29 Rge. 12  East  West County Pratt

RECOMPLETION FORMATION DESCRIPTION

Log  Sample

Name	Top	Bottom
Heebner	3707 (-1817)	
Douglas Shale	3763 (-1873)	
Douglas Sand	3791 (-1901)	
Brown Lime	3883 (-1993)	
Lansing	3896 (-2006)	
BKC	4283 (-2393)	
Marmaton	4299 (-2409)	
Kinderhook Shale	4409 (-2579)	
Viola	4490 (-2500)	

ADDITIONAL CEMENTING/SQUEEZE RECORD

Purpose:	Depth		Type of Cement	# Sacks Used	Type and Percent Additives
	Top	Bottom			
<input type="checkbox"/> Perforate					
<input type="checkbox"/> Protect Casing					
<input type="checkbox"/> Plug Back TD					
<input checked="" type="checkbox"/> Plug Off Zone	2801	2806	Common	100 sx	None

Shots Per Foot	PERFORATION RECORD		Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)
	Specify Footage of Each Interval Perforated		
4 SPF	4330-4335	4356-4360	Acidized w/1000 gal, 15% DSFE w/44 balls. Frac w/25,000 gal. X-link gel. 13,000# 20/40 and 9,000# 12/20.

PBTD 4562 Plug Type None


TUBING RECORD

Size 2" Set At 4380' Packer At None Was Liner Run Y X N

Date of Resumed Production, Disposal or Injection 2-17-90

Estimated Production Per 24 Hours Oil 6 Bbls. Water          Bbls. Gas-Oil-Ratio           
Gas          Mcf

Disposition of Gas:  
 Vented  Sold  Used on Lease (If vented, submit ACO-18.)



ORIGINAL  
INVOICE

INVOICE



A DIVISION OF HALLIBURTON COMPANY

P.O. BOX 951046  
DALLAS, TX 75395-1046

FEB 3 1990

INVOICE NO. 904002  
DATE 01/31/1990

WELL LEASE NO. WELL LOCATION STATE WELL OWNER

HEARN 1-29 PRATT KS SAME

SERVICE LOCATION CONTRACTOR JOB PURPOSE TICKET DATE

PRATT PRATT WELL SERVICE SQUEEZE PERFORATIONS 01/31/1990

ACCT. NO. CUSTOMER AGENT VENDOR NO. CUSTOMER P.O. NUMBER SHIPPED VIA FILE NO.

392900 THOM POOL COMPANY TRUCK 89780

DIRECT CORRESPONDENCE TO:

F G HOLL  
P O BOX 158  
BELPRE, KS 67519

SUITE 600  
COLORADO DERBY BUILDING  
WICHITA, KS 67202-0000

PRICE REF. NO.	DESCRIPTION	QUANTITY	U/M	UNIT PRICE	AMOUNT
000-117	PRICING AREA - MID CONTINENT MILEAGE	18	MI	2.20	39.60 *
		1	UNT		
009-134	CEMENT SQUEEZE	2779	FT	927.00	927.00 *
009-019		1	UNT		
504-308	STANDARD CEMENT	100	SK	5.35	535.00 *
507-775	HALAD-322	28	LB	5.60	156.80 *
500-207	BULK SERVICE CHARGE	100	CFT	.95	95.00 *
500-306	MILEAGE CMTG MAT DEL OR RETURN	84.85	TMI	.70	59.40 *
INVOICE SUBTOTAL					1,812.80
DISCOUNT-(BID)					271.92-
INVOICE BID AMOUNT					1,540.88
*-KANSAS STATE SALES TAX					65.49
*-PRATT COUNTY SALES TAX					15.41
INVOICE TOTAL - PLEASE PAY THIS AMOUNT					\$1,621.78

RECEIVED  
STATE PERFORATION COMMISSION  
MAY 22 1990  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
FEB 1990  
8910717121211

TERMS INVOICES PAYABLE NET BY THE 20<sup>TH</sup> OF THE FOLLOWING MONTH AFTER DATE OF INVOICE. UPON CUSTOMER'S DEFAULT IN PAYMENT OF CUSTOMER'S ACCOUNT BY THE LAST DAY OF THE MONTH FOLLOWING THE MONTH IN WHICH THE INVOICE IS DATED, CUSTOMER AGREES TO PAY INTEREST THEREON AFTER DEFAULT AT THE HIGHEST LAWFUL CONTRACT RATE APPLICABLE BUT NEVER TO EXCEED 18% PER ANNUM. IN THE EVENT IT BECOMES NECESSARY TO EMPLOY AN ATTORNEY TO ENFORCE COLLECTION OF SAID ACCOUNT, CUSTOMER AGREES TO PAY ALL COLLECTION COSTS AND