

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-081-20,526-0000 (of this well)  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR KANSAS NATURAL GAS, INC. OPERATORS LICENSE NO. #5269

ADDRESS P.O. Box #818 Hays, Kansas 67601 PHONE # (316) 675-8175 or

LEASE (FARM) BOATRIGHT #3 WELL NO. #3 WELL LOCATION Appr. C of NE COUNTY Haskell

SEC. 13 TWP. 29S RGE. 32W (E) or (W) TOTAL DEPTH 2752' ~~ETD~~ PLUG BACK TD 2750' KB

Check One:

OIL WELL \_\_\_\_\_ GAS WELL XXX D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 7/8" SET AT 571' CEMENTED WITH 285 SACKS

CASING SIZE 5 1/2" SET AT 2737' CEMENTED WITH 375 SACKS

PERFORATED AT 4-Shots Per foot 2693' to 2703' 2712' to 2722'

CONDITION OF WELL: GOOD XXXX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Pump 40/60 Pox (H) cement with 6% Bentonite  
to bottom of production perforations (approximately 2730') and set a 30 sack plug. Pull tubing  
to approximately 1875' (bottom of anhydrites) and set a 20 sack plug. Pull tubing to approximately  
580' (bottom of surface pipe) and set a 20 sack plug. Pull tubing to 30' from surface and set  
a 10 sack plug from there to surface. Plugging recommendation by Mr. Steve Durrant, with KCC.  
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACCURATE? yes No  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN In the very near future.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mr. Steve Lehning or Mr. Joe Ward PHONE # (316) 675-8175 or 275-7279

ADDRESS P.O. Box #815 Sublette, Kansas 67877

PLUGGING CONTRACTOR Dowell Schlumberger-Kansas Natural Gas LICENSE NO. \_\_\_\_\_

ADDRESS Mr. Garry Smith  
Ulysses, Kansas 67880 PHONE # (316) 356-1272

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Steve Lehning  
(Operator or Agent)

DATE: 8-14-89

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 22 1989 9-22-89  
WICHITA, KANSAS

①



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR  
KEITH R. HENLEY CHAIRMAN  
RICH KOWALEWSKI COMMISSIONER  
MARGALEE WRIGHT COMMISSIONER  
JUDITH McCONNELL EXECUTIVE DIRECTOR  
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION  
SHARI FEIST ALBRECHT, DIRECTOR  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, KS 67202-1286  
(316) 263-3238

DEC 25 1989

EXPIRES

September 25, 1989

NOTICE OF RECEIPT OF  
WELL PLUGGING APPLICATION

Kansas Natural Gas, Inc.  
P.O. Box 818  
Hays, KS 67601

Boatright #3  
Appx. C of NE ¼  
13-29-32W  
Haskell County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

*Shari Feist Albrecht*

Shari Feist Albrecht  
Director

District: #1 304 W. McArtor

Dodge City, KS 67801

(316) 225-6760