

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

Drill date 1-14-54

API # Not Applicable (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Kansas Natural Gas, Inc. KCC LICENSE # 5269
(owner/company name) (operator's)

6-93

ADDRESS P.O. Box 815 CITY Sublette

STATE Kansas ZIP CODE 67877 CONTACT PHONE # (316) 675-8185

LEASE Murphy WELL# 1 SEC. 33 T. 29 R. 32 (East/West)

App - C - NW - 1/4 SPOT LOCATION/QQQQ COUNTY Haskell

2790 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1370 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL ___ GAS WELL X D&A ___ SWD/ENHR WELL ___ DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 10 3/4" SET AT 519' CEMENTED WITH 400 SACKS

PRODUCTION CASING SIZE 7" SET AT 2754' CEMENTED WITH 700 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 2664'-2672' 2694'-2710' 2738'-2750'

ELEVATION 2910' 2915' T.D. 2754' PBD 2754' ANHYDRITE DEPTH 1855'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD ___ POOR X CASING LEAK yes JUNK IN HOLE yes

PROPOSED METHOD OF PLUGGING Recommendation by KCC. Set cast iron bridge plug at 1500'. Run tubing to 650'. Circulate 65/35 8% gel cement to surface. Dig cellar out at ground level and hook onto backside and pump cement to fill surface. Have an extra 100 sacks cement on location if needed. Cut casing off 5' below surface - weld cap and backfill.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Steve Lehning PHONE# (316) 675-8185

3-3-93

ADDRESS P.O. Box 815 City/State Sublette, KS 67877

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING CONTRACTOR Dowell Schlumberger, Kansas Natural Gas KCC LICENSE # NA
(company name) (contractor's)

ADDRESS Ulysses, KS 67880 PHONE # (316) 356-2372

PROPOSED DATE AND HOUR OF PLUGGING (if Known?) As soon as approved by KCC. CONSERVATION DIVISION
Wichita, Kansas

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-1-93 AUTHORIZED OPERATOR/AGENT: Steven M. Lehning
(signature)

1)