

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10154-00-00
API NUMBER Completed 1956

LEASE NAME A.W. Hines

RECEIVED

WELL NUMBER 1

3960 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 10 TWP. 32 RGE. 42 (29 or W)

COUNTY Morton

Date Well Completed 9-8-56

Plugging Commenced 3-26-02

Plugging Completed 3-28-02

MAY 15 2002 5-15-02

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

KCC WICHITA

LEASE OPERATOR Suerte Oil Company

ADDRESS Box 725 Howard KS. 67349

PHONE (316) 374-2000 OPERATORS LICENSE NO. 5177

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3-25-02 (date)

by Kevin Strube (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? NA

Producing Formation Shawnee-Nob Depth to Top 2802' Bottom 3221' T.D. 3260'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Admire</u>	<u>Gas</u>	<u>2802</u>	<u>2852</u>	<u>8 3/8</u>	<u>686</u>	<u>-</u>
<u>Woburnsee</u>	<u>Gas</u>	<u>2858</u>	<u>3008</u>			
<u>Elmont</u>	<u>Gas</u>	<u>3099</u>	<u>3166</u>	<u>5 1/2</u>	<u>3260</u>	<u>1110</u>
<u>Towka</u>	<u>Gas</u>	<u>3199</u>	<u>3221</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each so Mixed 25 SX cmt. down 2 3/4 w/ fluid level @ 2440. WOC Tag plug @ 2600. Recovered 1110 5 1/2 to TOP Ran 2 3/4 to 1100 Circ. hole w/ mud 50 SX 1100 to 950 50 SX 700 to 550 10 SX 40 to 0 Capped 8 3/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Suerte Oil Company

STATE OF Kansas COUNTY OF Elk, ss.

Maurice Perkins (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th the same are true and correct, so help me God.

(Signature) Maurice Perkins

(Address) P. O. Box 725 Howard, Kansas 67

JACQUELINE PERKINS
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 2-8-2004

SUBSCRIBED AND SWORN TO before me this 5th day of May, 2002

Jacqueline Perkins
Notary Public

My Commission Expires: 2-8-2004

OK