

15-129-00052-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Morton County, Sec. 13 Twp. 32S Rge. 42W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW/4

Lease Owner Parker Petroleum Co., Inc.

Lease Name Withroder Well No. 1

Office Address Box 791, Ponca City, Okla.

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed Sept. 17 19 57

Application for plugging filed Sept. 18 19 57

Application for plugging approved Sept. 20 19 57

Plugging commenced Sept. 21 19 57

Plugging completed Sept. 22 19 57

Reason for abandonment of well or producing formation non-commercial

If a producing well is abandoned, date of last production none 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation none Depth to top Bottom Total Depth of Well 5235 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Wabunsee	water	2832		8 5/8"	624'	none
Elmont	water	3078		5 1/2"	3506'	1508'
Topeka	water & gas	3138				
Lecompton	water	3374				
Morrow sd. (G zone)	water	4694				
Keyes sand	water	5110				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cement in csg. @ 3452. Bridge plug set @ 3400-3402 Bridge plug @ 3350-3352  
Bridge plug @ 3220-3222 Bridge plug @ 2970-2972

Plugged back to 2820 with sand and cement, used 2 sacks calseal and 15 sacks cement.

Shot pipe off @ 1508 - pulled pipe up to 1200' and filled 5-1/2" casing with mud.

Pulled 5-1/2" casing out of hole.

Pushed wiper plug to 650'. Dumped sand and rocks and bridged off. Dumped 20 sacks of cement and 2 sacks of calseal.

Set rock plug @ 35'. Filled up with 5 sacks cement and 2 sacks calseal.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kay Drilling Co., Inc.

Address Box 646, Ulysses, Kansas.

STATE OF Oklahoma, COUNTY OF Kay, ss. Melvin F. Endicott

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Melvin F. Endicott

Box 791, Ponca City, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 23 day of September, 1957

Dorcas Fern Alston

My commission expires 12-1-59

Notary Public.

PLUGGING  
FILE SEC 13 T 32 R 42W  
BOOK PAGE 46 LINE 23

SEP 27 2-27-57  
CONSERVATION DIVISION  
Wichita, Kansas

WITRODER #1

Well Record

Location: C NW Sec. 13-323-42W  
Morton County, Kansas

Commenced: July 29, 1957  
Completed: August 27, 1957  
(Rotary)

Operator: Parker Petroleum Company, Inc.  
P. O. Drawer 791  
Ponca City, Oklahoma

Contractor: Graham-Michaelis Drilling Company  
211 North Broadway  
Wichita 2, Kansas

Casing Record: 8 5/8" @ 681' w/400 sacks cement  
5 1/2" @ 3506' w/150 sacks cement

LOG

Surface rock and sand	427
Sand, clay & shells	1394
Lime & shale	2070
Shale & shells	2552
Lime & shale	3292
Lime	3323
Chalk shale & lime	3498
Lime & shale	5004
Lime, shale & sand	5119
Shale & lime	5201
Shale, sand & chalk	5235

STATE OF KANSAS )  
                          )  
COUNTY OF SEDGWICK )

The undersigned, GRAHAM-MICHAELIS DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING COMPANY

By John L. James  
John L. James Geologist.

Subscribed and sworn to before me  
this 27th day of August, 1957.

G. J. Greer

My commission expires: 1/7/61

RECEIVED  
STATE CONSERVATION COMMISSION

SEP 27 1957

PLUGGING CONSERVATION DIVISION
FILE SEC. 13 T 32 R 42W
BOOK PAGE 46 LINE 23
Wichita, Kansas