

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-151-21774-60-01

LEASE NAME Hanna-Wald

WELL NUMBER 1

1980 Ft. from S Section Line

3340 Ft. from E Section Line

SEC. 35 TWP. 28 SRGE. 13W (E) or (W)

COUNTY Pratt

Date Well Completed 5-1-92

Plugging Commenced 4-11-96

Plugging Completed 4-13-96

LEASE OPERATOR Plains Petroleum Operating Co.

ADDRESS P.O. Box 383 Lakin, Kansas 67860

PHONE# (316) 355-7838 OPERATORS LICENSE NO. 04253

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City 4-11-96

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippian Depth to Top 4407 Bottom 4427 T.D. 4698

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippian	Gas	4407	4427	8 5/8 5 1/2	378 4631	0 2840

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Pump 25 sks. of cement & 2 sks. of hulls to 4300'  
Pump 50 sks. of cement @ 780'  
Pump 50 sks. of cement @ 400'  
Pump 10 sks. of cement @ 40 to 0 Cut off & cap 8 5/8 4' below ground level  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Kearny, ss. 5-28-86

Don K. Wilken (Employee of Operator) MAY 28 1996 of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Don K. Wilken CONSERVATION DIVISION WICHITA, KS

(Address) P.O. Box 383; Lakin, KS. 67860

SUBSCRIBED AND SWORN TO before me this 24th day of May, 19 96

Laurel Patton Notary Public

My Commission Expires: October 10, 1998

