

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-151-21,617-0000

LEASE NAME Eubank Trust

WELL NUMBER "A" #1

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 33 TWP. 28 RGE. 13 (E) or (W)

COUNTY Pratt

Date Well Completed 6-21-85

Plugging Commenced 6-21-85

Plugging Completed 6-22-85

LEASE OPERATOR American Energies Corporation

ADDRESS 575 4th Financial Center, Wichita, Kansas 67202

PHONE#( 310 263-5785 OPERATORS LICENSE NO. 5399

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4625

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		<u>0</u>	<u>310</u>	<u>8 5/8"</u>	<u>6-14-85</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with 120 sxs 60/40 Lite, 3% cc, 2% gel as follows: 790'-50 sxs; 330'-40 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; water well- 5 sxs. Job by Buie. Plug down at 1:15 a.m. on June 22, 1985.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Oilfield Services, Inc. License No. 5149

Address P. O. Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Arnie Little

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) Arnie Little

(Address) P. O. Box 329, Pratt, Kansas 67124



SUBSCRIBED AND SWORN TO before me this 25th day of June, 19 85

Mary L. Tjaden

Notary Public  
STATE CORPORATION COMMISSION

My Commission Expires: 3/22/88

6-26-85 JUN 26 1985 Form CP-4  
Revised 08-84



**Oilfield Services, Inc.**

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Eubank Trust "A" #1  
 NW SW SW Sec. 33-28S-13W  
 Pratt County, Kansas  
 Commenced: 6-14-85  
 Completed: 6-22-85  
 API #15-151-21,617-000  
 Operator: American Energies Corporation

Depth		Formation	Remarks
From	To		
0	314	Sand, Clay	Ran 7 joints (300') new, 24#, 8 5/8" surface casing. Set at 310' with 200 sxs Common, 2% gel, 3% cc. Cement did circulate. Job by Buie. Plug down at 4 p.m. on June 14, 1985.
314	1400	Sand, Shale	
1400	2000	Clay, Shale	
2000	2645	Lime, Shale	
2645	3045	Shale	
3045	4625	Lime, Shale	
		T.D.	RTD 4625'
			Plug well with 120 sxs 60/40 Lite, 3% cc, 2% gel as follows: 790'-50 sxs; 330'-40 sxs; 40'-10 sxs with solid bridge; rathole-15 sxs; water well-5 sxs. Job by Buie. Plug down at 1:15 a.m. on June 22, 1985. State Plugger was out of the Dodge City, Kansas office.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

*Arnie Little*  
 ARNIE LITTLE, VICE-PRESIDENT



*Mary L. Tjaden*  
 NOTARY PUBLIC

My Commission Expires:  
3/22/89

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 26 1985