


15-151-00230-0000

STATE OF KANSAS  
CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

### WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pratt County. Sec. 33 Twp. 28 Rge. 13W (E) (W)  
 Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines 100' W C SE SE NE  
 Lease Owner A. D. Allison & Co., & J. G. Ripstra  
 Lease Name FLEMMING Well No. 1  
 Office Address 715 Brown Building, Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
 Date well completed 8-11-50 19\_\_\_\_  
 Application for plugging filed 8-11-50 19\_\_\_\_  
 Application for plugging approved 8-11-50 19\_\_\_\_  
 Plugging commenced 8-13-50 19\_\_\_\_  
 Plugging completed 8-13-50 19\_\_\_\_  
 Reason for abandonment of well or producing formation Dry hole  
 If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4658 Feet  
 Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand and shale	Water	70	190	8-5/8	395	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Laid down drill pipe, filled hole with heavy mud. Set bottom plug at 395; mixed and poured 15 sacks cement thru drill pipe. Set top plug at 30' mixed and poured 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to A. D. Allison & Co., Inc.,  
 Address 715 Brown Building, Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
J. A. Allison (employee of owner) or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J Allison  
715 Brown Building, Wichita, Kansas.  
 (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1950  
Neal Schack Notary Public.  
 My commission expires 7-22-53

28-3278-s 4-50-10M

AUG 18 1950

STATE OF KANSAS  
 CORRELATION  
818-50

**PLUGGING**  
 FILE SEC-33T 28 R-13W  
 BOOK PAGE-21 LINE-27

15-151-00230-0000

LOCATION: SE SE NW 33-28-13W., - Pratt County, Kansas.

FARM: FLEMMING #1

CASING RECORD:

OWNER: A. D. Allison & Co.,  
and J. G. Ripstra

8-5/8 395'

CONTR: A. D. Allison & Co., Inc.

COMM: 7-16-50

COMP: 8-11-50

PROD: D & A

FORMATION	DEPTH
Clay	70
Sand and shale	190
Shale and red bed	375
Red bed and shells	615
Anhydrite and shale	750
Shale and shells	820
Shale, shells and red bed	1170
Salt	1335
Shale and shells	1900
Shale and lime	1935
Lime and shale	2035
Shale and shells	2150
Lime	2175
Lime, hard	2200
Lime	2296
Shale and shells	2535
Lime	2595
Shale	2600
Shale and lime	2660
Lime, shells and shale	2730
Lime and shale	3065
Shale	3091
Lime	3125
Shale, lime and shells	3205
Lime	3675
Shale and lime	3970
Lime	4378
Shale	4384
Lime	4505
Sand - coring	4513
coring	4520
Lime	4545
Lime and shale	4606
Lime	4658 T. D.

TOPS:

Lansing	3950
Mississippian	4384
Viola	4433
Simpson	4496
Arbuckle	4606

Cored 4505 - 4513. Recovered 6 1/2'.  
D. S. T. 4500 - 4513. Recovered 30'  
very slightly oil cut mud in 1 1/2 hrs.

Cored 4513 - 4520. Recovered 4 1/2'.  
D. S. T. 4500 - 4520. Recovered  
95' mud and water in 1 1/2 hours.

Certified true copy of drillers log.

By J. A. Allison

**PLUGGING**  
 SEC 33 T 28 R 13 W  
 BOOK PAGE 21 LINE 27