

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
Rev. 12-15-80

FEB 16 1982

CONSERVATION DIVISION
Wichita, Kansas

15-151-21076-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 32 TWP. 28S RGE. 13 XR/W
Location as in quarters or footage from lines:
NE $\frac{1}{4}$

Locate Well
correctly on above
Section Platt.

Lease Owner Eagle Petroleum Corp.
Lease Name Bryan Well No. 1
Office Address 520 S. Holland, Wichita, KS 67209
Character of Well (Completed as Oil, Gas or Dry Hole): dry hole
Date Well Completed 2-1-82
Application for plugging filed 2-11-82
Plugging commenced 2-1-82
Plugging completed 2-1-82
Reason for abandonment of well or producing formation
Dry-abandoned

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well _____

Producing formation _____ Depth to top _____ bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged as follows:

1st plug at 620' Cemented w/60 sks
2nd plug at 360' Cemented w/40 sks
Mud to 40' Solid Bridge w/10 sks
10 sks rat hole
3 sks water well
Cement 123 sks common 2% Gel, 3% CC
Plug set and job complete at 7:30 a.m. 2-1-82

Witnesses: Richard Brown, Charlie Ross, Jack Weimaster

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

STATE OF Kansas COUNTY OF Sedgwick, ss.

D.W. Smith (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.


(Signature) D.W. Smith
D.W. Smith, Sec. Treas.
(Address)

P.O. Box 18595, Wichita, KS 67218

SUBSCRIBED AND SWORN TO before me this 2nd day of Feb., 19 82

LuAnn Voran
LuAnn Voran Notary Public.

My Commission expires: _____





P.O. Box 18595 / Wichita, KS 67218

15-151-21076-0000

Wichita (316) 262-3071
(316) 685-1401

Great Bend (316) 793-5285

Mobile (316) 672-5663
Unit 2904

Rig #1 (316) 672-5663
Unit 2905

DRILLERS' WELL LOG

Bryan #1
NE 1/4, Sec. 32-28S-13W
Pratt County, Kansas

Commenced: 1-14-82
Completed: 2-1-82

Operator: Eagle Petroleum Corp.

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
From	To		
0	850	Sand	Set 363' of used 8 5/8" csg. 23#
850	3,300	Sand and Shale	set at 371'. Cement w/350 sks common
3,300	4,330	Shale and Lime	3% CC, 2% gel. Job complete at 8:15 p.m.
4,330	4,420	K.C. Lansing	1-16-82.
4,420	4,580	Mississippian	
4,580	4,601	Arbuckle	D & A.

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1982

CONSERVATION DIVISION
Wichita Kansas

Plugged Well.

1st plug at 620' w/60 sks.
2nd plug at 360' w/40 sks.
Solid bridge plug at 40' w/10 sks.
Rathole 10 sks., waterwell 3 sks.
Cemented w/common 2% gel, 3% CC.
Job complete 7:30 a.m. 2-1-82.

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.

I, the undersigned, being duly sworn on oath state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

LuAnn Voran
LuAnn Voran, Notary Public

LANDMARK ENERGY CORP.

D.W. Smith
D.W. Smith, Sec.-Treas.