


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pratt County. Sec. 32 Twp. 28S Rge. (E1) 13W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines C - SE/4 SE/4 NE/4  
Lease Owner Lion Oil Company & R. W. Rine Drilling Company  
Lease Name McMinn Well No. 1  
Office Address P. O. Box 639, Pratt, Kansas (Lion Oil Company)  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-18 19 54  
Application for plugging filed (Verbal) 7-18 19 54  
Application for plugging approved (Verbal) 7-18 19 54  
Plugging commenced 7-18 19 54  
Plugging completed 7-18 19 54  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4615 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	433'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with mud from 4615' to 300'.  
Plugged back with plug and 20 sacks of cement from 300' to 240'. Plugged back with mud from 240' to 35'. Plugged back with plug and 10 sacks of cement from 35' to top of surface casing.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 26 1954 7-26-54  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R. W. Rine Drilling Company  
Address 320 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss.  
Vernon Hayes (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Vernon Hayes  
P. O. Box 639, Pratt, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of July, 19 54

My commission expires August 29, 1955 Don Daubel Notary Public.

PLUGGING  
FILED SEC 32 T 28 R 13W  
COOK PAGE 49 LINE 20

15-154-00350-0000

CTR. OF SE SE NE  
SECTION 32-28S-13W  
PRATT COUNTY, KANSAS

MCMINN WELL NO. 1

CONTRACTOR: THE R. W. RINE DRILLING COMPANY

STARTED: JUNE 29, 1954

COMPLETED: JULY 18, 1954

LOG

SAND & CLAY	0 - 210	
RED BED	210 - 435	8-5/8" csg. @ 433' w/300 sx.
RED BED & SHELLS	435 - 765	
ANHYDRITE	765 - 800	
RED BED, SHELLS & SHALE	800 - 1330	SYFO @ 1000' - 1 <sup>0</sup> , SALT @ 1200'
SHALE & SHELLS	1330 - 1940	SYFO @ 1500' - 1 <sup>0</sup> , 1980' - 3/4 <sup>0</sup>
SHALE & LIME	1940 - 3200	SYFO @ 2500' - 0 <sup>0</sup> , 3000' - 1 <sup>0</sup>
LIME	3200 - 3480	
LIME & SHALE	3480 - 3773	SYFO @ 3500' - 1 1/2 <sup>0</sup>
SAND, LIME & SHALE	3773 - 3930	
LIME	3930 - 4315	
LIME & SHALE	4315 - 4362	
LIME & CHERT	4362 - 4425	
SHALE & CHERT	4425 - 4533	
SHALE & LIME	4533 - 4615	TOTAL DEPTH - PLUGGED 7-18-54.

STATE OF KANSAS )  
COUNTY OF SEDGWICK)

I, R. M. GREEN, DO HEREBY CERTIFY THAT THE ABOVE IS A TRUE AND ACCURATE LOG OF THE MCMINN WELL NO. 1, LOCATED IN THE CENTER OF THE SE SE NE, SECTION 32-28S-13W, PRATT COUNTY, KANSAS.

*R. M. Green*  
\_\_\_\_\_  
ASSISTANT SECRETARY

SUBSCRIBED TO AND SWORN BEFORE ME THIS 23 DAY OF JULY, 1954.

*Judy Kiefer*  
\_\_\_\_\_  
NOTARY PUBLIC

MY COMMISSION EXPIRES: 7-31-57

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 26 1954

PLUGGING  
FILE SEC 32 T 28 R 13W  
BOOK PAGE 49 LINE 20

CONSERVATION DIVISION  
Wichita, Kansas