



15-151-10495-0000

The following information concerns the H & T Drilling Company No. 1 Scott, located in the SEc 32-28S-13W, Pratt County, Kansas.

Elevation is 1927 feet. Surface hole was made September 7, 1945. At 879 feet 10-inch pipe was cemented. Top of Lansing was 3912, top of Mississippian 4375, top of Viola 4405 with slight porosity, some staining and no odor at 4405-11. This was not considered a commercial show.

Top of Simpson shale 4470, Simpson dolomite 4480. Soft at 4488-90. Good odor and show of oil in sandy dolomite. Cored at 4490-97. Recovered 7 feet; 2 feet dolomitic sandstone with irregular porosity and saturation; 3 feet friable firm, well saturated sandstone; 2 feet lenticular sandy shale with mottled saturation; good odor for whole core.

Top of Arbuckle was 4579, porosity 4605-08 and 4615-20. There was no odor in wet samples. Total depth 4628. The well was plugged back to 4493, 4483 feet 5 $\frac{1}{2}$ " casing was cemented.

