

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80
 RECEIVED
 JAN 25 1983
 CONSERVATION DIVISION
 Wichita, Kansas
 1-25-83
 6-051-20301-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Pratt S $\frac{1}{2}$ NE-SE SEC. 28 TWP 28S RGE. 3 R/W
 Location as in quarters or footage from lines:

			X

Locate Well
 correctly on above
 Section Platt.

Lease Owner Ronald Russ Prater, Inc.
 Lease Name Moore Well No. 1
 Office Address 240 Rock Road Wichita, Kansas 67206
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas
 Date Well Completed Sept. 16, 1975
 Application for plugging filed Oct. 6, 1982
 Plugging commenced Dec. 29, 1982
 Plugging completed Dec. 31, 1982
 Reason for abandonment of well or producing formation

Not economical to produce
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bud Metz
 Producing formation Viola Depth to top 4365 bottom 4365 T.D. 4525
 Show depth and thickness of all water, oil and gas formations. Rotary TD 4527

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Viola						
Surface Water	fresh	0	255'	10 3/4"		
				4 1/2"	2325'	1954'
Indian Cave	Gas	0	2325'	4 1/2"	2325'	1920'
Viola	Gas	0	4463'	2 7/8"	4468'	2563'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


2 7/8 cemented with 25 sacks 50/50 Poz mix 2% gel, 3% CC, plug set at 4165'. Dia Log cut tubing at 2563', cemented 4 1/2" intermediate string with 25 sacks 50/50 Poz mis 2% gel 3% CC, plug set at 2280'. Dia Log cut 4 1/2" at 1920'. 10 3/4" surface pipe plugged with 3 sacks hulls, 10 sacks gel, 50 sacks 50/50 Poz mis, 2% gel, 3% CC, 10 sacks gel, 100 sacks 50/50 Poz mix 2% gel, 3% CC, plug down at 2:00. Max. pressure 700# ISIP 300#, Ready mix to top of surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pratt Well Service, Inc. Box 847 Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Pratt, ss.

Judy Baird (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Judy Baird
Box 847 Pratt, Ks.
 (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of January, 19 83

Charlene M. Dudgey
 Notary Public.

My Commission expires: 9/10/86

DRILLERS LOG

15-151-20301-0000

MOORE #1

CASING RECORD:

10 3/4" set at 262'
with 200 sack cement

TOTAL DEPTH:
4525'

OPERATOR: Ronald Russ Driller, Inc.

CONTRACTOR: Search Drilling Company

COMMENCED: September 1, 1975

COMPLETED: September 16, 1975

DESCRIPTION:

C 3/2 184 NE,
Section 28-283-13W
Pratt County,
Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Shale	0	50	
Sand	50	185	
Redbed and Shale	185	263	
Redbed and Shale	263	288	
Redbed and Shale	288	536	
Redbed	536	1339	
Shale	1339	1862	
Broken Lime, Shale, Chert	1862	1966	
Shale, Lime and Chert	1966	2115	
Shale and Lime	2115	2222	
Shale and Lime	2222	2252	
Shale and Lime	2252	2440	
Shale and Lime	2440	2583	
Shale and Lime	2583	2717	
Shale and Lime	2717	2800	
Shale and Lime	2800	2927	
Shale and Lime	2927	2936	
Lime and Lime	2936	2980	
Lime and Shale and Sand	2980	2984	
Lime and Shale	2984	3091	
Lime and Shale	3091	3182	
Lime and Shale	3182	3292	
Lime and Shale	3292	3398	
Lime and Shale	3398	3482	
Lime and Shale	3482	3587	
Lime and Shale	3587	3696	
Lime	3696	3833	
Lime and Shale	3833	3908	
Lime and Shale	3908	3920	
Lime	3920	3940	
Lime	3940	4025	
Lime	4025	4100	
Lime	4100	4180	
Lime	4180	4258	
Lime	4258	4330	
Lime	4330	4352	
Lime	4352	4392	
Lime and Chert	4392	4405	
Lime and Chert	4405	4418	
Sand and Shale	4418	4469	
Shale	4469	4525	

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1982

CONSERVATION DIVISION
Wichita, Kansas

Run 20 joints of new
4 1/2" casing set at
262' with 100 sacks
cement cost of 10' call.
Plus was down at 10:15 AM

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

William J. Froelich, Jr.
William J. Froelich, Jr.

Subscribed and sworn to before me this 16th day of September, 1975

My commission expires:
February 19, 1977

Maxine Dressen
Maxine Dressen

Notary Public

MAXINE DRESSEN
NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. FEB. 19, 1977

15-15120301-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION - OBSERVATION DIVISION
3830 South Meridian - Box 17027
Wichita, Kansas 67217

FORM C-2

DATA AND AFFIDAVIT

(On Cementing in Surface or Drive Pipe and required by Rule 82-2-123 of the Commission for compliance with Section 55-136, 55-137 and 55-138, 1947 Supplement to G. S. Kansas 1935)

LEASE OWNER Ronald Russ Prater, Inc.

OFFICE ADDRESS #235 - 240 North Rock Road - Wichita, Kansas 67206

LEASE NAME Moore WELL NO. 1 COUNTY Pratt (W)

EXACT SPOT LOCATION C Se NE SE SEC. 28 TWP. 28S RGE. 13 (E)

CONTRACTOR Search Drilling Company

OFFICE ADDRESS P. O. Box 18148 - Wichita, Kansas 67218

Drilled with (~~Cable~~) or (Rotary) tools: Date pipe set September 1, 1975

SURFACE HOLE DATA

SURFACE PIPE DATA

Size of Hole 13 3/4" Cgr. (new) or (~~used~~) size 10 3/4 Wt. 40#

Depth 262' Where set 254.49'

METHOD OF CEMENTING

Cement: Amount and kind 200 Sacks of Common Cement

Method: (By Service Co., Lamp, Top., etc.) Service Company

Est. Height Cement behind pipe _____

GROUND WATER INFORMATION

Depth to bottom of lowest fresh water producing stratum 160

Name of lowest fresh water producing stratum unknown

Surface elevation of well 1943 KB

RECEIVED
STATE CORPORATION COMMISSION

OCT 27 1982

ADDITIONAL INFORMATION

CONSERVATION DIVISION
Wichita, Kansas

(Additional information may be submitted on separate sheet)

A F F I D A V I T

STATE OF Kansas COUNTY OF Sedgwick SS.

I, William J. Froelich, Jr., of the Search Drilling Company, being first duly sworn on oath, state that I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

William J. Froelich, Jr.
William J. Froelich Jr.

Subscribed and sworn to before me on this 16th day of September 19 75

My Commission Expires:
February 19, 1977

Maxine Dressen
Maxine Dressen

MAXINE DRESSEN
NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. FEB. 19, 1977