

15151-00066000

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Pratt County, Sec. 26 Twp. 28S Rge. (E) 13(W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NW
Lease Owner Flynn Oil Co.
Lease Name Elwell Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed May 24 19 49
Application for plugging filed May 24 19 49
Application for plugging approved May 24 19 49
Plugging commenced 3 P.M. May 24 19 49
Plugging completed 9 P.M. May 24 19 49
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough - 3414 18th St., Great Bend, Ks
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4636 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	cemented at 375'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

#1 plug set at 372 - 20 sacks cement - filled to 25' of cellar - with rotary mud
#2 plug set 25' - 10 sacks cement - which filled pipe to bottom of cellar

RECEIVED
Conservation Div.
JUN 1 1949
STATE CORPORATION
COMMISSION
KANSAS

6-1-49

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Corbett-Barbour Drilling Co.
Address 820 Kennedy Bldg., Tulsa, Okla.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
A. M. Barbour (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. M. Barbour

820 Kennedy Bldg., Tulsa, Okla.
(Address)

Subscribed AND SWORN to before me this 31 day of May, 19 49

Merry Jane Wienecke
Notary Public.

My commission expires

July 27, 1949

PLUGGING
FILE SEC 26-28-132
BOOK PAGE 98 LINE 340

2-48-15M

15-151-0006-0000

M. P. BARBOUR, PRES.
 A. M. BARBOUR, JR., VICE-PRES.
 ED W. PRIBYL, VICE-PRES.
 A. M. BARBOUR, SECY.-TREAS.

CORBETT-BARBOUR DRILLING CO.

820 KENNEDY BUILDING

TULSA, OKLAHOMA

FLYNN OIL COMPANY

BLWELL NO. 1
 SW SW NW of Section 26-28S-15W
 Pratt County, Kansas

10-3/4" O.D. casing cemented at 378'
 Dry hole

Drilling commenced 4-29-49
 Drilling completed 5-22-49

FROM	TO	FORMATION	REMARKS
0'	230'	Sand & shells	
230	375	Sand, shale & shells	10-3/4" O.D. casing cemented with 895 sacks bulk cement with 2 sacks C. C. cement at 378'.
375	615	Shale, shells & red bed	
615	1115	Red bed & shells	
1115	1700	Shale & shells	
1700	1960	Shale & broken lime	
1960	2095	Shale & lime	
2095	2140	Broken lime & shale	
2140	2230	Lime	
2230	2520	Lime & shale	
2520	2761	Shale	
2761	2810	Shale & lime	
2810	3035	Sandy shale	
3035	3160	Lime & shale	
3160	3335	Broken lime	
3335	3475	Lime	
3475	3593	Lime & shale	
3593	3812	Lime	
3812	3838	Douglas sand	
3838	4240	Lime	
4240	4329	Lime & shale	
4329	4340	Miss. lime	
4340	4361	Shale & lime	
4361	4392	Lime & chert	
4392	4408	Shale & lime	
4408	4426	Lime & chert	
4426	4439	Sandy shale & lime	
4439	4469	Lime	
4469	4485	Lime & chert	
4485	4520	Lime	
4520	4524	Lime & sand	
4524	4534	Shale & sand	
4534	4542	Lime & sand	
4542	4546	Sand & chert	
4546	4547	Sand	

PLUGGER
 FULL SEC - T - R
 BOOK PAGE - LINE

RECEIVED
 Conservation Div.
 JUN - 1 1949
 STATE CORPORATION
 COMMISSION
 KANSAS

FLYNN OIL COMPANY
Elwell No. 1

FROM	TO	FORMATION	REMARKS
4547'	4559'	Shale & sand	
4559	4566	Chert & sandy shale	
4566	4575	Shale & lime	
4575	4593	Shale & shells	
4593	4606	Shale, chert & lime	
4606	4622	Arb. lime	
4622	4651	Shale, lime & chert	
4631	4636	Lime	Dry hole.
T.D. 4636'			

This is a true copy of the drillers' log as shown on our drilling tickets.

CORBETT-BARBOR DRILLING CO.

A. M. Barbour
A. M. Barbour

Subscribed and sworn to before me this 31st day of May, 1949.

Merry Jane Wienecke
Notary Public

My Commission expires July 27, 1949

PLUGGING
ALL SEC. 26, 28, 30, 32
BOOK PAGE 27 LINE 34

RECEIVED
Conservation Div.
JUN - 1 1949
STATE CORPORATION
COMMISSION
KANSAS