


15-151-20827-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pratt County. Sec. 7 Twp. 28S Rge. 13WE7W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C-NW NE
Lease Owner Par Petroleum, Inc.
Lease Name McFall Well No. 1
Office Address Box 280, Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed December 17, 1980
Application for plugging filed Verbal Application 19____
Application for plugging approved Verbal Approval 19____
Plugging commenced December 17, 1980
Plugging completed December 17, 1980
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 14,550'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	357'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,550 ft. (rotary total depth) to 370 ft. Set plug at 370 ft. and cemented with 70 sacks cement. Filled hole with heavy rotary mud from 370 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 20 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent ~~xxxxxxx~~ of owner) ~~xxxxxxx~~
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water-Suite 10, Wichita, KS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 80

My commission expires July 25, 1982

Elsie Willison
Notary Public.
Wichita, Kansas
6/1981
RECEIVED
CONSERVATION DIVISION
Wichita, Kansas

1-6-81

KANSAS DRILLERS LOG

COMPANY Par Petroleum, Inc.

SEC. 7 T. 28S R. 13W

FARM McFall NO. 1

LOC. C-NW NE

COUNTY Pratt

ROTARY TOTAL DEPTH 4,550'

COMM. December 6, 1980 COMP. December 17, 1980

CONTRACTOR H-30, INC. (Rig #3)

ISSUED December 29, 1980

CASING

10 3/4" Set at 357' cemented w/300 sxs cement

8 5/8"

5 1/2"

4 1/2"

ELEVATION 1,924' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	115'
Red Bed	380'
Red Bed and Shale	1,107'
Shale, Shells and Lime	1,728'
Shale and Lime	1,968'
Lime and Shale	2,360'
Shale and Lime	2,600'
Lime and Shale	4,455'
Lime	4,550'
Rotary Total Depth	4,550'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
Dean Britting

State of Kansas)
County of Sedgwick) SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 29th day of December, 1980.

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

