




STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Kiowa County, Sec. 27 Twp. 29 Rge. (E) 18 (W)  
Location as "NE/CNW/SW" or footage from lines C NW SW  
Lease Owner Misco Supply Company  
Lease Name Mollie Greenwood Well No. 1  
Office Address 257 N. Broadway, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed June 15 19 71  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced July 26 19 71  
Plugging completed August 4 19 71  
Reason for abandonment of well or producing formation depleted  
If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4950 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	367'	8 5/8"	367'	none
		0	4940'	7"	4940'	2241.68

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded back to 4900' and dumped 6 sacks of cement.

Set 20' rock bridge at 260'. Plug well with 6 yards of ready mix cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 2 1971  
CONSERVATION DIVISION  
Wichita, Kansas

9-2-71

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor PIPE PULLERS, INC.  
Address Box 486, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of August, 19 71

My commission expires Feb. 10, 1975

George A. Meyer  
Notary Public.

15-097-10134-0000

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

COPY

Company- OHIO OIL COMPANY  
Farm- Mollie Greenwood No. 1


SEC. 27 T. 29 R. 18W  
C NW SW

Total Depth. 4950'  
Comm. 8-1-56  
Shot or Treated.  
Contractor.  
Issued. 12-1-56

Comp. 8-23-56

County Kiowa

KANSAS



Elevation. 2198' KB

Production. 183 BOPD

Figures indicate Bottom of Formations.

MEASUREMENTS ARE KELLEY BUSHING MEASUREMENTS

surface clay	40
shale	385
shale & red beds	819
shale	880
red beds & shale	1115
Anhydrite	1140
shale & lime shells	1317
shale	1950
lime & shale	2130
lime	2205
lime & shale	2340
lime	3185
lime & shale	3400
lime	3715
lime & shale	3820
lime	4114
Heebner shale	4122
lime & shale	4304
lime & shale (Lansing Kansas City)	4754
lime & shale (Marmaton section)	4904
Mississippi Chert	4950
Total Depth	

SCOUT TOPS:

Lansing	4296
Mississippi	4904

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 16 1971  
CONSERVATION DIVISION  
Wichita, Kansas