

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Kiowa County, Sec. 27 Twp. 29 Rge. (E) 18(W)

Location as "NE/CNW/SE/SW" or footage from lines C SE SW

Lease Owner Misco Industires, Inc.

Lease Name Greenwood Well No. 6

Office Address 257 N. Broadway, Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed _____ 19____

Application for plugging filed June 7 1974

Application for plugging approved June 10 1974

Plugging commenced Aug. 12 1974

Plugging completed Aug. 22 1974

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4979 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			400'	10"	400'	none
			4975'	7"	4975'	2670.84

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded back to 4140' and dumped 6 sacks of cement.

Set 10' rock bridge at 200' and plugged well with 4 yards of ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1974 8-30-74

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor PIPE PULLERS, INC. (If additional description is necessary, use BACK of this sheet)

Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss. Evelyn Roth

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

Subscribed and sworn to before me this 28th day of August, 1974

My commission expires July 16, 1978

JENNY KASSELMAN
NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY COMM. EXP. JULY 16, 1978

Notary Public.

15-097-10139-0000


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- OHIO OIL CO.
Farm- Mollie Greenwood No. 6

SEC. 27 T. 29 R. 18W
C SE SW

Total Depth. 4979'
Comm. 2-25-57 Comp. 3-15-57
Shot or Treated.
Contractor.
Issued. 9-14-57

County Kiowa
KANSAS



Elevation. 2223' RB

Production. I.P.F. 86 BO &
42 BWPD

Figures indicate Bottom of Formations.

	CASING:	
10 3/4"	400'	
7"	4975'	
clay & red beds	179	
red beds	1050	
red bed & shale	1756	
red bed, shale & salt	2188	
shale & shells	2355	
anhydrite, shale, salt	2437	
shale & anhydrite	2535	
shale & lime	2869	
lime	3032	
lime & shale	3500	
lime	3591	
lime & shale	3663	
lime	3856	
lime & shale	3974	
lime	4084	
lime & shale	4116	
lime	4185	
lime & shale	4251	
lime	4280	
lime & shale	4450	
lime	4800	
lime, shale & chert	4835	
lime & chert	4864	
lime & shale	4906	
lime	4932	
lime & chert	4979	
Total Depth		

TOPS:	
Brown Lime	4320
Lansing-Kansas City	4337
Mississippi Chert	4936

Show of gas & oil from 4937' to 4979'!

RECEIVED
STATE CORPORATION COMMISSION
MAY 1 1973
CONSERVATION DIVISION
Wichita, Kansas