

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-097-21,149-0000

LEASE NAME YOST "A" #2

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

330 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 29 TWP. 29S RGE. 18 **XXXX (W)**

COUNTY Kiowa

Date Well Completed 10-8-85

Plugging Commenced 10-8-85

Plugging Completed 10-8-85

LEASE OPERATOR TXO Production Corp.

ADDRESS 155 N. Market, Suite 1000, Wichita, KS 67202

PHONE#(316) 269-7600 OPERATORS LICENSE NO. 5171

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Unknown

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation N/A Depth to Top Bottom T.D. 5015'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	435'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well as follows: @ 1160' pumped 50 sxs, @ 480' pumped 40 sxs, wooden plug @ 40' followed by 10 sxs cmt to surface, 10 sxs in rathole, 15 sxs in mousehole. Used a total of 125 sxs, 60-40 Pozmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor FWA Drilling Co., Inc. License No. 6165

Address P.O. Box 850980, Yukon, OK 73085-0980

STATE OF COUNTY OF , ss.

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry W. Collins

(Address) Jerry W. Collins  
November 15, 1985

SUBSCRIBED AND SWORN TO before me this 15<sup>th</sup> day of November, 1985

Connie F. Koehler

Notary Public

My Commission Expires: July 10, 1988

RECEIVED

STATE CORPORATION COMMISSION

Form CP-4  
Revised 08-84

11-18-85 NOV 18 1985

Connie F. Koehler  
NOTARY PUBLIC  
State of Kansas  
MY APPT. EXPIRES 7/10/88