

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 097-21,253-0000

LEASE NAME HADLEY

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

3960' Ft. from S Section Line

3960' Ft. from E Section Line

LEASE OPERATOR BUTTONWOOD PETROLEUM, INC.

SEC. 16 TWP. 29 SRGE. 18W (E) or (W)

ADDRESS 9 E. 4th St. Suite 605 Tulsa, Ok. 74103

COUNTY KIOWA

PHONE # (918) 587-7585 OPERATORS LICENSE NO. 8222

Date Well Completed 2-26-88

Character of Well GAS

Plugging Commenced 10-26-88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-26-88

The plugging proposal was approved on October 19, 1988 (date)

by PAUL LUTHI DODGE CITY DISTRICT (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation MISSISSIPPIAN Depth to Top 4950' Bottom 4954' T.D. 5050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
MISSISSIPPIAN	GAS	4950'	4954'	8-5/8"	525'	NONE
				4-1/2"	5049'	2521.95'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.  
CIBP @ 4900' w/2 sx Cement on top. Loaded hole w/9#/Gal mud w/Hulls Spotted 50sx 60/40 Pozmix w/6% gel from 1215'-979'; Loaded hole w/9#/Gal mud w/Hulls Spotted 75 sx 60/40 Pozmix w/6% gel from 607'-281' & 10 sx 60/40 Pozmix w/6% gel from 40'-3'. Welded on Steel plate with operator Identification and ACO-1.  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor BUTTONWOOD PETROLEUM/WESTERN CO. License No. DE 8222

Address 9 E. 4th St. Suite 605 Tulsa, Ok. 74103

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: BUTTONWOOD PETROLEUM, INC.

STATE OF OKLAHOMA COUNTY OF ELLIS, ss.

JIM MABRY, FIELD SUPERINTENDENT (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jim Mabry

(Address) Rte. 1 Box 126 Arnett, Ok. 73832

SUBSCRIBED AND SWORN TO before me this 14th day of Dec, 19 88

E E Martin  
 Notary Public

My Commission Expires: Nov. 30-1992

RECEIVED  
 CONSERVATION COMMISSION  
 12-19-88  
 WICHITA, KANSAS

PLUGGING PROCEDURE

HADLEY # 1  
SEC. 16 T29S R18W  
KIOWA COUNTY KANSAS

WELL GEOMETRY: TD 5050'.

- 8-5/8" 24# J-55 CASING @ 525'.
- 4-1/2" 10.5# J-55 CASING @ 5049'.
- 2-3/8" 4.7# 8RD EUE TUBING @ 4976'.
- 196 3/4" RODS PLUS 20' OF PONY RODS.
- 2" X 1-1/2" X 12' RHBC PUMP.

1. MIRU WELL SERVICE RIG.
2. ND PUMPING TEE & TOH WAREHOUSING RODS.
3. NU 7-1/16" X 3000# DBL RAM MANUAL BOP.
4. TOH LAYING DOWN TUBING. LEAVE 650' STANDING IN DERRICK.  
RU TOM HANSEN COMPANY AND SET CIBP @ 4900'. FREE POINT AND  
JET CUT 4-1/2" CASING. RD WIRELINE TOOLS.
5. LOAD HOLE WITH 9.0#/GAL. MUD & TOH LAYING DOWN CASING.
6. TTH W/ OPENENDED TUBING AND SPOT 105 SX CLASS H CEMENT F/625'-  
425'. PULL 5 STANDS AND REVERSE OUT. WAIT FOUR HOURS AND TAG  
PLUG. TOH LAYING DOWN TUBING. ND BOP & WELLHEAD.
7. CUT OFF 8-5/8" CASING AND DUMP 10 SX CLASS H CEMENT @ SURFACE.  
WELD ON PLATE.
8. FLUSH SALT WATER DISPOSAL LINE AND FILL W/FRESH WATER. TACK BULL PLUG  
IN VALVE. DISCONNECT GAS LINE, FILL W/FRESH WATER AND PLUG OFF.  
RESTORE LOCATION.

175 SX 60/40 For  
w/ 6% GEL

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1988

CONSERVATION DIVISION  
Wichita, Kansas