

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County. Sec. 17 Twp. 29S Rge. 18 (E) (W)

Location as "NE/CNW'SW" or footage from lines C NW NW SE

Lease Owner Gulf Oil Corporation et al

Lease Name Ezra Kinsall Well No. 1

Office Address Box 9010, Amarillo, Texas 79105

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed 4 - 20 19 55

Application for plugging filed 2 - 16 19 70

Application for plugging approved 2 - 17 19 70


Plugging commenced 4 - 20 19 70

Plugging completed 4 - 24 19 70

Reason for abandonment of well or producing formation Producing below economic limit.

If a producing well is abandoned, date of last production January 19 70

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Russel Biberstien

Producing formation Marmaton & Mississippi Depth to top 4836' Bottom 4998' Total Depth of Well 5003 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Mississippi	Gas	4975'	5003'	8 5/8"	361'	None
Marmaton	Oil & Gas	4810'	4975'	5 1/2"	5041'	2297'
Lansing	Water	4371'	4810'			
Douglas	Water	4217'	4246'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from - feet to - feet for each plug set.

Pumped 100 sax cement down casing to 4700' with 37 viscosity mud.  
Cement plug 4998' to 4700'. Mud 4700' to surface.  
Ripped off and pulled 2297' of 5 1/2" 14# casing.  
Ran tubing to 385' and spotted 35 sax cement plug from 385' to 280'.  
Filled hole with mud to 55'.  
Rock bridge from 55' to 45'.  
Cement from 45' to bottom of cellar (25 sax).

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas

5-6-70

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clark Oil Field Service  
Address Medicine Lodge, Kansas

STATE OF Texas, COUNTY OF Potter, ss.  
J. D. Richards (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. D. Richards  
P.O. Box 9010, Amarillo, Texas 79105

(Address)

SUBSCRIBED AND SWORN to before me this 4th day of May, 1970

(Signature) Dorothy B. Scott  
Notary Public.

My commission expires 6-1-71

15-097-10050-0001

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 17 1970  
CONSERVATION DIVISION  
Wichita, Kansas

FORMATION RECORD

	From	To
Red Bed	0	185
Red Bed & Shale		325
Shale		1220
Shale & Shells		1565
Red Bed & Shells		1824
Red Bed & Shale		2040
Shale & Shells		2165
Shale & Lime		3227
Shale		3332
Lime & Shale		3543
Shale		3621
Shale & Lime		4426
Lime		4583
Lime & Shale		4987
Total Depth		5045

EZRA KINSALL M