

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-097-21390-00-00
Spot: NWSENW Sec/Twnshp/Rge: 24-29S-18W
1750 feet from N Section Line, 1650 feet from W Section Line
Lease Name: JENKINS Well #: 1-24
County: KIOWA Total Vertical Depth: 4950 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4947	2440	WITH 160 SX CMT
SURF	8.625	429		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/01/2015 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 30 SX CMT WITH 100# HULLS. PLUG AT 1100' WITH 10 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2015 3:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

5/29/15: PUMPED 30 SX CMT WITH 100# HULLS. PRESSURED TO 1500#. 6/1/15: TAGGED CMT AT 4200'. 1ST PLUG AT 1120' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 461' WITH 50 SX CMT. 3RD PLUG AT 44' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4836	4875		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

6/10/15 CRM

District: 01

Signed


(TECHNICIAN)

RECEIVED
JUN - 2 2015
KCC DODGE CITY

KCC WICHITA
JUN 03 2015
RECEIVED