

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-20594-00-00
Spot: E2SWSWNW Sec/Twnshp/Rge: 13-24S-15W
3029 feet from S Section Line, 4704 feet from E Section Line
Lease Name: ENGLISH-REID Well #: 3
County: STAFFORD Total Vertical Depth: 4352 feet

Operator License No.: 5474
Op Name: NORTHERN LIGHTS OIL COMPANY, LL
Address: PO BOX 164
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3760		WITH 2 SX CMT
CIBP		4311		
PROD	5.5	4351	0	WITH 125 SX CMT
SURF	8.625	518		WITH 325 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2015 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: PRESTON DREILING Company: DREILING EXPLORATION LLC Phone: (785) 639-2099

Proposed Plugging Method: CIBP @ 3750' WITH 2 SX CMT. PERFORATE AT 1020'. RUN TBG IN TO 1020'. CIRCULATE CMT INSIDE/OUTSIDE 5 1/2" CASING TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/21/2015 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3760' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 5 1/2" CASING AT 1020'. RUN TBG TO 1020'. PUMP DOWN TBG WITH 215 SX CMT. CMT CIRCULATED TO SURFACE UP 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
4281	4286		
4276	4281		
4272	4277		
4253	4258		
4131	4134		
4128	4129		
4106	4111		
4096	4103		
3806	3812		

KCC WICHITA
JUN 05 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

6/10/15 ckm

District: 01

Signed Stephen P Pfeifer
(TECHNICIAN)

RECEIVED
JUN - 2 2015
KCC DODGE CITY

SA