

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-03283-00-00
Spot: NENENE Sec/Twnshp/Rge: 11-16S-12W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: THILL B Well #: 1
County: BARTON Total Vertical Depth: 3378 feet

Operator License No.: 30601
Op Name: NORTHSTAR INVESTMENTS, INC.
Address: 13735 PINNACLE
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3360		135 SX
SURF	8.625	263		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/19/2015 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DEAN BRITTING Company: NORTHSTAR INVESTMENTS Phone: (316) 733-8996

Proposed
Plugging
Method:

Ordered 10 sx gel, 350 sx 60/40 pozmix 4% gel cement and 400 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/19/2015 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 760' and 250'. Ran tubing to 2930' and pumped 10 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1400' and pumped 70 sx cement w/200 # hulls. Pulled tubing to 750' and pumped 50 sx cement. Pulled tubing to 250'. Circulated cement to surface w/75 sx cement on the casing. Pulled tubing. Tied to casing and circulated cement to surface w/40 sx cement on the surface pipe.

GPS: 38.68030 -098.60984

Perfs:

Top	Bot	Thru	Comments
3329	3349		
2912	2917		

KCC WICHITA
MAY 28 2015
RECEIVED

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

6/10/15 CKM

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

MAY 20 2015