

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-113-21363-01-00
Spot: NWNWNWNW Sec/Twnshp/Rge: 36-19S-1W
275 feet from N Section Line, 272 feet from W Section Line
Lease Name: SHADE TREE Well #: 25-1H
County: MCPHERSON Total Vertical Depth: 2944 feet

Operator License No.: 34358
Op Name: ORCA OPERATING COMPANY LLC
Address: 427 S. BOSTON, STE 400
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3934		200 SX
SURF	9.58	402		200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/14/2015 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: ED.PATTERSON Company: CONSOLIDATED OIL WELL SRVICE Phone: (918) 618-2717

Proposed Plugging Method: Per KCC Rules & Regulations. Set CIBP @ +3510, fill casing with > 50 bentonite mud, set cement plugs: 20 sx on top of CIBP, 15 bbls, 400 ft to surface. Cut off 3 ft below GL & weld on ID plate with well name & location.

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2015 12:00 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

SET CIBP @ 2860' APPROVED BY JEFF KLOCK. PRESSURED TESTED TO 300# PASSED. SPOTTED 35 SKS ON CIBP CLASS A COMMON. 2% CC. PULLED 8 JOINTS PUMPED 92 BBLS GEL. PULLED UP TO 422' CIRCULATE 85 SKS TO SURFACE. CUT BACKSIDE OFF. RAN 1" DOWN BACKSIDE. PUMPED 70 SKS ON BACKSIDE. THEN 20 SKS TOP OFF. CHECK TOP PLUG 4/17/15 - AT SURFACE. WELDED CAP AND ID PLATE ON WELL.



Perfs:

Remarks: CONSOLIDATED ELDORADO TICKET #45873 -- TMD IS 5184'

Plugged through: TBG

District: 02

Signed

(TECHNICIAN)

6/10/15 CKM

Received
KANSAS CORPORATION COMMISSION

JUN 09 2015

CONSERVATION DIVISION
WICHITA, KS