

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-069-20453-01-00
Spot: NWNWNWSW Sec/Twnshp/Rge: 17-26S-29W
2515 feet from S Section Line, 5052 feet from E Section Line
Lease Name: CIRCLE D 2629 Well #: 1-18H
County: GRAY Total Vertical Depth: 4984 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5669		WITH 100 SX CMT
COND 20		120		WITH 10 SX CMT
PROD 7		5719	1731	WITH 340 SX CMT
SURF 9.625		1600		WITH 700 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/01/2015 3:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: STEVE JOHNSON Company: SANDRIDGE EXPLORATION & PR Phone: (405) 397-1986

Proposed Plugging Method: SET CIBP @ 5669' WITH 50-100 SX CMT. PLUG AT 1650' WITH 60 SX CMT. PLUG AT 850' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2015 5:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5669' WITH 100 SX CMT. 1ST PLUG AT 1640' WITH 60 SX CMT. 2ND PLUG AT 850' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5719	7493	OH	

KCC WICHITA
JUN 05 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES. TMD = 7493'

Plugged through: TBG

District: 01

Signed Larry Harris ALBERT
(TECHNICIAN)

RECEIVED
JUN - 2 2015
KCC DODGE CITY

6/10/15 ckm