

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-069-20454-01-00
Spot: SESESE Sec/Twnshp/Rge: 21-26S-29W
273 feet from S Section Line, 473 feet from E Section Line
Lease Name: TOEWS 2629 Well #: 4-21H
County: GRAY Total Vertical Depth: 5092 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	120		WITH 10 SX CMT
PROD	7	5769	1676	WITH 340 SX CMT
SURF	9.625	1553		WITH 735 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/27/2015 3:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: STEVE JOHNSON Company: SANDRIDGE EXPLORATION & PR Phone: (405) 397-1986

Proposed Plugging Method: CIBP @ 5200' WITH 50 SX CMT. CIRCULATE HOLE WITH MUD. PLUG AT 1600' WITH 100 SX CMT. PLUG AT 850' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/27/2015 5:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

TAG EXISTING CIBP @ 5190' & SPOT 50 SX CMT. 1ST PLUG AT 1601' WITH 100 SX CMT. 2ND PLUG AT 852' WITH 50 SX CMT. 3RD PLUG AT 63' WITH 30 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
7450	7475		
6808	6810		
6790	6792		
6748	6750		
6682	6684		
6666	6668		
6616	6618		
6574	6576		
6520	6522		
6478	6480		
6079	6081		
6065	6067		
6029	6031		
6009	6011		
5980	5982		
5872	5875		
5808	7475		

KCC WICHITA
JUN 05 2015
RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY ORR ENTERPRISES.

Plugged through: TBG

Per plugging appl.

MTD = 7566'

TVD 5092' 6/10/15 JEM

District: 01

Signed Larry Harris PIRT II
(TECHNICIAN)

RECEIVED
JUN - 2 2015
KCC DODGE CITY

JA