

To: 1 051755 12-8
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 057-20488-0000
150' N of
NW SE, SEC. 22, T 29 S, R 22 W
2130 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address: 110 N. Market Ste. 205
Wichita, KS 67202

Lease Name Hearne "A" Well # 1
County Ford
Well Total Depth 5400 175.50 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 517

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 1 p.m. Day: 8 Month: 12 Year: 19 93
Plugging proposal received from Vernon Duntz
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 4 1/2" at 5397' w/150 sx cement, PBTD 5352', Perfs at 5280-85' (below BP at 5272')
1st plug sand back to 5200' and dump 4 sx cement on top of sand ^{5259-64'} through bailer,
2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 175 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 2 p.m. Day: 8 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 5200' and dumped 4 sx cement on top
of sand through bailer,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs.
hulls, released 8 5/8" wiper plug and pumped 175 sx cement.
Maximum pressure 600 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2826' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (and/or my agent) observe this plugging.

DATE 12-14-93
WV. NO. 39522

Signed Richard W. Lusk
STATE CORPORATION COMMISSION
TECHNICIAN
RECEIVED
DEC 10 1993